



Kerr-McGee Oil & Gas OnShore LP  
1999 Broadway, Suite 3700, Denver, Colorado 80202  
303-296-3600 • Fax 303-296-3601

March 1, 2007

Ms. Diana Mason  
Division of Oil, Gas and Mining  
P.O. Box 145801  
Salt Lake City, UT 84114-6100

RE: State 1021-32J  
T10S-R21E  
Section 32: NWSE  
1802' FSL, 2149' FEL  
Uintah County, Utah

Dear Ms. Mason:

Kerr-McGee Oil & Gas Onshore LP, formerly known as Westport Oil and Gas Company, L.P. has submitted a permit to drill the captioned well to test the Wasatch and Mesaverde formations. The well is located at an exception location to State Rule 649-3-2 (State Wide). The well location is less than 920' from the proposed State 1021-32O well which may produce from the same pool. Both wells are located within the same lease and the proximity between wells does not interfere with the correlative rights of the royalty and working interest owners. Kerr-McGee owns 100% of the leasehold in the offset lands.

Kerr-McGee requests your approval of this exception location. If you have any questions, call me at 720-264-2618. Thank you for your assistance.

Sincerely,

A handwritten signature in black ink, appearing to read 'W. Chris Latimer'.

W. Chris Latimer, CPL  
Senior Landman

cc: Raleen White

RECEIVED  
MAR 14 2007  
DIV. OF OIL, GAS & MINING

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐  
(highlight changes)

<b>APPLICATION FOR PERMIT TO DRILL</b>				5. MINERAL LEASE NO: <b>ML-21577</b>	6. SURFACE: <b>State</b>
1A. TYPE OF WORK: <b>DRILL</b> <input checked="" type="checkbox"/> <b>REENTER</b> <input type="checkbox"/> <b>DEEPEN</b> <input type="checkbox"/>				7. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
B. TYPE OF WELL: <b>OIL</b> <input type="checkbox"/> <b>GAS</b> <input checked="" type="checkbox"/> <b>OTHER</b> _____ <b>SINGLE ZONE</b> <input type="checkbox"/> <b>MULTIPLE ZONE</b> <input checked="" type="checkbox"/>				8. UNIT or CA AGREEMENT NAME:	
2. NAME OF OPERATOR: <b>KERR MCGEE OIL &amp; GAS ONSHORE L.P.</b>				9. WELL NAME and NUMBER: <b>STATE 1021-32J</b>	
3. ADDRESS OF OPERATOR: <b>1368 S 1200 E</b> CITY <b>VERNAL</b> STATE <b>UT</b> ZIP <b>84078</b>			PHONE NUMBER: <b>(435) 781-7024</b>	10. FIELD AND POOL, OR WILDCAT: <b>NATURAL BUTTES</b>	
4. LOCATION OF WELL (FOOTAGES)  AT SURFACE: <b>1802'FSL, 2149'FEL</b> <b>621992X</b> <b>39.901639</b>  AT PROPOSED PRODUCING ZONE: <b>44176054</b> <b>-109.572957</b>				11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: <b>NWSE 32 10S 21E</b>	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: <b>17.9 MILES SOUTH OF OURAY, UTAH</b>				12. COUNTY: <b>UINTAH</b>	13. STATE: <b>UTAH</b>
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) <b>1802'</b>		16. NUMBER OF ACRES IN LEASE: <b>640.00</b>		17. NUMBER OF ACRES ASSIGNED TO THIS WELL: <b>40.00</b>	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) <b>REFER TO TOPO C</b>		19. PROPOSED DEPTH: <b>9,060</b>		20. BOND DESCRIPTION: <b>RLB0005237</b>	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): <b>5313'GL</b>		22. APPROXIMATE DATE WORK WILL START:		23. ESTIMATED DURATION:	

24. PROPOSED CASING AND CEMENTING PROGRAM						
SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT			SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT	
<b>12 1/4"</b>	<b>9 5/8</b>	<b>H-40</b>	<b>32.3#</b>	<b>1,800</b>	<b>265 SX CLASS G</b>	<b>1.18 YIELD 15.6 PPG</b>
<b>7 7/8"</b>	<b>4 1/2</b>	<b>I-80</b>	<b>11.6#</b>	<b>9,060</b>	<b>1930 SX 50/50 POZ</b>	<b>1.31 YIELD 14.3 PPG</b>

25. ATTACHMENTS	
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:	
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER  <input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN  <input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER

NAME (PLEASE PRINT) <b>SHEILA UPCHEGO</b>	TITLE <b>SENIOR LAND ADMIN SPECIALIST</b>
SIGNATURE	DATE <b>3/14/2007</b>

(This space for State use only)

API NUMBER ASSIGNED: **243047-309133**

**Approved by the  
Utah Division of  
Oil, Gas and Mining**

APPROVAL:

Date: **06-25-07**  
(See Instructions on Reverse Side)  
By:


**RECEIVED**

**MAR 16 2007**

DIV. OF OIL, GAS & MINING

# T10S, R21E, S.L.B.&M.

N89°55'18"E - 5356.30' (Meas.)



## LEGEND:

- └─┘ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

(NAD 83)  
 LATITUDE = 39°54'05.75" (39.901597)  
 LONGITUDE = 109°34'25.09" (109.573636)  
 (NAD 27)  
 LATITUDE = 39°54'05.87" (39.901631)  
 LONGITUDE = 109°34'22.61" (109.572947)

## Kerr-McGee Oil & Gas Onshore LP


Well location, STATE #1021-32J, located as shown in the NW 1/4 SE 1/4 of Section 32, T10S, R21E, S.L.B.&M., Uintah County, Utah.

## BASIS OF ELEVATION

TWO WATER TRIANGULATION STATION LOCATED IN THE NW 1/4 OF SECTION 1, T10S, R21E, S.L.B.&M., TAKEN FROM THE BIG PACK MTN NE, QUADRANGLE, UTAH, UTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5238 FEET.

## BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.



## CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEY MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

**ROBERT L. KAY**  
 REGISTERED LAND SURVEYOR  
 REGISTRATION NO. 18431  
 STATE OF UTAH

**UINTAH ENGINEERING & LAND SURVEYING**  
 85 SOUTH 200 EAST - VERNAL, UTAH 84078  
 (435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 12-13-06	DATE DRAWN: 12-18-06
PARTY L.K. J.M. P.M.	REFERENCES G.L.O. PLAT	
WEATHER COLD	FILE Kerr-McGee Oil & Gas Onshore LP	

**STATE 1021-32J  
NW/SE SEC. 32, T10S, R21E  
UINTAH COUNTY, UTAH  
ML-21577**

**ONSHORE ORDER NO. 1**

***DRILLING PROGRAM***

**1. Estimated Tops of Important Geologic Markers:**

<u>Formation</u>	<u>Depth</u>
Uinta	0- Surface
Green River	916'
Top of Birds Nest Water	1159'
Mahogany	1683'
Wasatch	4077'
Mesaverde	6917'
MVU2	7920'
MVL1	8433'
TD	9060'

**2. Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:**

<u>Substance</u>	<u>Formation</u>	<u>Depth</u>
Water	Green River	916'
	Top of Birds Nest Water	1159'
	Mahogany	1683'
Gas	Wasatch	4077'
Gas	Mesaverde	6917'
Gas	MVU2	7920'
Gas	MVL1	8433'
Water	N/A	
Other Minerals	N/A	

**3. Pressure Control Equipment (Schematic Attached)**

*Please refer to the attached Drilling Program.*

**4. Proposed Casing & Cementing Program:**

*Please refer to the attached Drilling Program.*

**5. Drilling Fluids Program:**

*Please refer to the attached Drilling Program.*

**6. Evaluation Program:**

*Please refer to the attached Drilling Program.*



7. **Abnormal Conditions:**

Maximum anticipated bottomhole pressure calculated at 9060' TD, approximately equals 5617 psi (calculated at 0.62 psi/foot).

Maximum anticipated surface pressure equals approximately 3624 psi (bottomhole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

8. **Anticipated Starting Dates:**

*Drilling is planned to commence immediately upon approval of this application.*

9. **Variances:**

*Please refer to the attached Drilling Program.*

10. **Other Information:**

*Please refer to the attached Drilling Program.*



# KERR-McGEE OIL & GAS ONSHORE LP

## DRILLING PROGRAM

COMPANY NAME KERR-McGEE OIL & GAS ONSHORE LP DATE March 14, 2007  
 WELL NAME STATE 1021-32J TD 9,060' MD/TVD  
 FIELD Natural Buttes COUNTY Uintah STATE Utah ELEVATION 5,313' GL KB 5,328'  
 SURFACE LOCATION NW/SE SEC. 32, T10S, R21E 1802'FSL, 2149'FEL BHL Straight Hole  
 Latitude: 39.901597 Longitude: 109.573636  
 OBJECTIVE ZONE(S) Wasatch/Mesaverde  
 ADDITIONAL INFO Regulatory Agencies: UDOGM (SURF & MINERALS), Tri-County Health Dept.

GEOLOGICAL			MECHANICAL		
LOGS	FORMATION	DEPTH	HOLE SIZE	CASING SIZE	MUD WEIGHT
		40'		14"	
			12-1/4"	9-5/8", 32.3#, H-40, STC	Air mist
Catch water sample, if possible, from 0 to 4,077'					
	Green River @	0,916'			
	Top of Birds Nest Water @	1,159'			
	Mahogany @	1,683'			
	Preset f/ GL @				
	1,800' MD				
Note: 12.25" surface hole will usually be drilled ±400' below the bottom of lost circulation zone. Drilled depth may be ±200' of the estimated set depth depending on the actual depth of the loss zone.					
Mud logging program TBD Open hole logging program f/ TD - surf csg					
	Wasatch @	4,077'	7-7/8"	4-1/2", 11.6#, I-80 or equivalent LTC casing	Water/Fresh Water Mud 8.3-11.5 ppg
	Mverde @	6,917'			
	MVU2 @	7,920'			
	MVL1 @	8,433'			
	TD @	9,060'			Max anticipated Mud required 11.5 ppg



# **KERR-McGEE OIL & GAS ONSHORE LP** **DRILLING PROGRAM**

## **CASING PROGRAM**

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-40'						
SURFACE	9-5/8"	0 to 1800	32.30	H-40	STC	2270	1370	254000
						0.66*****	1.63	4.99
PRODUCTION	4-1/2"	0 to 9060	11.60	I-80	LTC	7780	6350	201000
						2.27	1.17	2.19

- 1) Max Anticipated Surf. Press.(MASP) (Surface Casing) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point)
- 2) MASP (Prod Casing) = Pore Pressure at TD - (.22 psi/ft-partial evac gradient x TD)
- (Burst Assumptions: TD = 11.5 ppg) .22 psi/ft = gradient for partially evac wellbore
- (Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)
- MASP 3425 psi
- \*\*\*\*\* Burst SF is low but csg is much stronger than formation at 2000'. EMW @ 2000' for 2270# is 21.8 ppg or 1.13 psi/ft

## **CEMENT PROGRAM**

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE Option 1	LEAD	500	Premium cmt + 2% CaCl + .25 pps flocele	215	60%	15.60	1.18
	TOP OUT CMT (1)	200	20 gals sodium silicate + Premium cmt + 2% CaCl + .25 pps flocele	50		15.60	1.18
	TOP OUT CMT (2)	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
SURFACE Option 2		<b>NOTE: If well will circulate water to surface, option 2 will be utilized</b>					
	LEAD	1500	Prem cmt + 16% Gel + 10 pps gilsonite +.25 pps Flocele + 3% salt BWOC	170	35%	11.00	3.82
	TAIL	500	Premium cmt + 2% CaCl + .25 pps flocele	180	35%	15.60	1.18
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
PRODUCTION	LEAD	3,570'	Premium Lite II + 3% KCl + 0.25 pps celloflake + 5 pps gilsonite + 10% gel + 0.5% extender	390	60%	11.00	3.38
	TAIL	5,490'	50/50 Poz/G + 10% salt + 2% gel +.1% R-3	1540	60%	14.30	1.31

\*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

\*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

## **FLOAT EQUIPMENT & CENTRALIZERS**

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe.
PRODUCTION	Float shoe, 1 jt, float collar. Centralize first 3 joints & every third joint to top of tail cement with bow spring centralizers.

## **ADDITIONAL INFORMATION**

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. Test to 5,000 psi (annular to 2,500 psi) prior to drilling out. Record on chart recorder & tour sheet. Function test rams on each trip. Maintain safety valve & inside BOP on rig floor at all times. Kelly to be equipped with upper & lower kelly valves.

Drop Totco surveys every 2000'. Maximum allowable hole angle is 5 degrees.

Most rigs have PVT Systems for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING ENGINEER:

Brad Laney



DATE:

DRILLING SUPERINTENDENT:

Randy Bayne

DATE:

# 5M BOP STACK and CHOKE MANIFOLD SYSTEM



STATE 1021-32J  
NW/SE SEC. 32, T10S, R21E  
Uintah County, UT  
ML-21577

ONSHORE ORDER NO. 1

***MULTI-POINT SURFACE USE & OPERATIONS PLAN***

**1. Existing Roads:**

Refer to Topo Map A for directions to the location.

Refer to Topo Maps A and B for location of access roads within a 2-mile radius.

Refer to Topo Maps A and B for location of access roads within a 2 mile radius.

All existing roads will be maintained and kept in good repair during all drilling and completion operations associated with this well.

**2. Planned Access Roads:**

Approximately 0.15 +/- miles of new access road is proposed. Refer to Topo Map B for the location of the proposed access road.

The upgraded and new portions of the access road will be crowned and ditched with a running surface of 18 feet and a maximum disturbed width of 30 feet. Appropriate water control will be installed to control erosion.

*Existence of pipelines; maximum grade; turnouts; major cut and fills, culverts, or bridges; gates, cattle guards, fence cuts, or modifications to existing facilities were determined at the on-site.*

The access road was centerline flagged during time of staking.

Surfacing material may be necessary, depending upon weather conditions.

Surface disturbance and vehicular traffic will be limited to the approved location and approved access route. Any additional area needed will be approved in advance.

**3. Location of Existing Wells Within a 1-Mile Radius:**

Please refer to Topo Map C.

**4. Location of Existing & Proposed Facilities:**

*The following guidelines will apply if the well is productive.*

All production facilities will be located on the disturbed portion of the well pad and at a minimum of 25 feet from the toe of the back slope or the top of the fill slope.

A dike will be constructed completely around those production facilities which contain

fluids (i.e., production tanks, produced water tanks, and/or heater/treater). These dikes will be constructed of compacted subsoil, be impervious, hold 100% of the capacity of the largest tank, and be independent of the back cut.

All permanent (on-site six months or longer) above the ground structures constructed or installed, including pumping units, will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the five state Rocky Mountain Inter-Agency Committee.

All facilities will be painted within six months of installation. Facilities required to comply with the Occupational Safety and Health Act (OSHA) will be excluded. The required color is Carlsbad Canyon, standard color number 2.5Y 6/2.

Any necessary pits will be properly fenced to protect livestock and prevent wildlife entry.

Approximately 880' +/- of 4" steel pipeline is proposed from the location to an tie-in point. Refer to Topo Map D.

Approximately 833' +/- of 4" steel pipeline is proposed from the location to an tie-in point. Refer to Topo Map D.

**5. Location and Type of Water Supply:**

Water for drilling purposes will be obtained from Dalbo Inc.'s underground well located in Ouray, Utah, Sec. 32, T4S, R3E, Water User Claim #43-8496, Application #53617.

Water will be hauled to location over the roads marked on Maps A and B.

No water well is to be drilled on this lease.

**6. Source of Construction Materials:**

Surface and subsoil materials in the immediate area will be utilized.

Any gravel will be obtained from a commercial source.

**7. Methods of Handling Waste Materials:**

Drill cuttings will be contained and buried in the reserve pit.

Drilling fluids, including salts and chemicals, will be contained in the reserve pit. Upon termination of drilling and completion operations, the liquid contents of the reserve pit will be removed and disposed of at an approved waste disposal facility within 120 days after drilling is terminated.

The reserve pit will be constructed on the location and will not be located within natural drainage, where a flood hazard exists or surface runoff will destroy or damage the pit walls. The reserve pit will be constructed so that it will not leak, break, or allow discharge of liquids.

A plastic reinforced liner and felt will be used, it will be a minimum of 20 mil thick, with sufficient bedding used to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash or scrap that could puncture the liner will be disposed of in the pit.

Any spills of oil, gas, salt water, or other noxious fluids will be immediately cleaned up and removed to an approved disposal site.

A chemical porta-toilet will be furnished with the drilling rig.

Garbage, trash, and other waste materials will be collected in a portable, self-contained, fully enclosed trash cage during operations. No trash will be burned on location.

All debris and other waste material not contained in the trash cage will be cleaned up and removed from the location immediately after removal of the drilling rig.

Any open pits will be fenced during the operations. The fencing will be maintained until such time as the pits are backfilled.

No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

Any produced water from the proposed well will be contained in a water tank and will then be hauled By truck to one of the pre-approved disposal sites: RNI, Sec. 5, T9S, R22E, NBU #159, Sec. 35, T9S, R21E, Ace Oilfield, Sec. 2, T6S, R20E, MC&MC, Sec. 12, T6S, R19E.

**8. Ancillary Facilities:**

None are anticipated.

**9. Well Site Layout: (See Location Layout Diagram)**

The attached Location Layout Diagram describes drill pad cross-sections, cuts and fills, and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s), and surface material stockpile(s).

Please see the attached diagram to describe rig orientation, parking areas, and access roads.

The reserve pit will be lined, and when the reserve pit is closed, the pit liner will be buried below plow depth.

All pits will be fenced according to the following minimum standards:

39 inch net wire will be used with at least one strand of barbed wire on top of the net wire. Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.

The net wire shall be no more than two inches above the ground. The barbed wire shall be three inches over the net wire. Total height of the fence shall be at least 42 inches.

Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.

Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.

All wire shall be stretched, by using a stretching device, before it is attached to corner posts.

The reserve pit fencing will be on three sides during drilling operations, and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

Location size may change prior to the drilling of the well due to current rig availability. If the proposed location is not large enough to accommodate the drilling rig the location will be re-surveyed and a Form 9 shall be submitted.

**10. Plans for Reclamation of the Surface:**

*Producing Location:*

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, materials, trash, and debris not required for production.

Immediately upon well completion, any hydrocarbons in the pit shall be removed in accordance with 43 CFR 3162.7-1.

A plastic, nylon reinforced liner will be used, it shall be torn and perforated before backfilling of the reserve pit.

Before any dirt work associated with location restoration takes place, the reserve pit shall be as dry as possible. All debris in it will be removed. Other waste and spoil materials will be disposed of immediately upon completion of operations.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 90 days from the date of well completion, weather permitting.

To prevent surface water (s) from standing (ponding) on the reclaimed reserve pit area, final reclamation of the reserve pit will consist of "mounding" the surface three feet above surrounding ground surface to allow the reclaimed pit area to drain effectively.

Upon completion of backfilling, leveling, and recontouring, the stockpiled topsoil will be spread evenly over the reclaimed area(s).

*Dry Hole/Abandoned Location:*

Abandoned well sites, roads, and other disturbed areas will be restored as near as practical to their original condition. Where applicable, these conditions include the re-establishment of irrigation systems, the re-establishment of appropriate soil conditions, and re-establishment



of vegetation as specified.

All disturbed surfaces will be recontoured to the approximate natural contours, with reclamation of the well pad and access road to be performed as soon as practical after final abandonment.

Reseeding operations will be performed after completion of other reclamation operations.

**11. Surface Ownership:**

SITLA  
675 East 500 South, Suite 500  
Salt Lake City, UT 84102

**12. Other Information:**

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, the approved Plan of Operations, and any applicable Notice of Lessees. The Operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative to ensure compliance.

The Operator will control noxious weeds along Rights-Of-Way for roads, pipelines, well sites, or other applicable facilities.

A Class III archaeological survey will be submitted when report becomes available.

This location is not within 460' from the boundary of the Natural Buttes Unit, nor is it within 460' of any non-committed tract lying within the boundaries of the Unit.

**13. Lessee's or Operators's Representative & Certification:**

Sheila Upchego  
Senior Land Admin Specialist  
Kerr-McGee Oil & Gas Onshore LP  
1368 South 1200 East.  
Vernal, UT 84078  
(435) 781-7024

Randy Bayne  
Drilling Manager  
Kerr-McGee Oil & Gas Onshore LP  
1368 South 1200 East  
Vernal, UT 84078  
(435)781-7018

Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Kerr-McGee Oil & Gas Onshore LP agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.

Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by State Surety Bond #RLB0005237.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed by the Operator, its contractors, and subcontractors in conformity with this plan and the terms and conditions under which it is approved.



Sheila Upchego

3/14/2007

Date

# Kerr-McGee Oil & Gas Onshore LP

STATE #1021-32J

SECTION 32, T10S, R21E, S.L.B.&M.

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF STATE HIGHWAY 88; TURN LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 17.0 MILES TO OURAY, UTAH; PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 15.6 MILES ON THE SEEP RIDGE ROAD TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 1.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTH; TURN RIGHT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 0.15 MILES TO THE BEGINNING OF THE PROPOSED ACCESS FOR THE #1021-32N TO THE EAST; FOLLOW ROAD FLAGS IN AN EASTERLY, THEN NORTHEASTERLY DIRECTION APPROXIMATELY 0.2 MILES TO THE PROPOSED #1021-32N AND THE BEGINNING OF THE PROPOSED ACCESS FOR THE #1021-32H TO THE NORTHEAST; FOLLOW ROAD FLAGS IN A NORTHEASTERLY DIRECTION APPROXIMATELY 0.5 MILES TO THE BEGINNING OF THE PROPOSED ACCESS TO THE SOUTH; FOLLOW ROAD FLAGS IN A SOUTHWESTERLY DIRECTION APPROXIMATELY 0.15 MILES TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 48.9 MILES.

# Kerr-McGee Oil & Gas Onshore LP

## STATE #1021-32J

LOCATED IN UINTAH COUNTY, UTAH  
SECTION 32, T10S, R21E, S.L.B.&M.




PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: EASTERLY



PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

CAMERA ANGLE: SOUTHERLY



- Since 1964 -

**UELS** Uintah Engineering & Land Surveying  
85 South 200 East Vernal, Utah 84078  
435-789-1017 uels@uelsinc.com

LOCATION PHOTOS

12 15 06  
MONTH DAY YEAR


PHOTO

TAKEN BY: L.K.

DRAWN BY: C.P.

REVISED: 00-00-00





# **LEGEND:**

○ PROPOSED LOCATION



**Utah Engineering & Land Surveying**  
 85 South 200 East Vernal, Utah 84078  
 (435) 789-1017 \* FAX (435) 789-1813



**Kerr-McGee Oil & Gas Onshore LP**

**STATE #1021-32J**


**SECTION 32, T10S, R21E, S.L.B.&M.**

**1802' FSL 2149' FEL**

**TOPOGRAPHIC** 12 15 06  
**MAP** MONTH DAY YEAR  
 SCALE: 1:100,000 DRAWN BY: C.P. REVISED: 00-00-00







# **LEGEND:**

— EXISTING ROAD  
 - - - PROPOSED ACCESS ROAD

**N**

**Kerr-McGee Oil & Gas Onshore LP**

**STATE #1021-32J**  
**SECTION 32, T10S, R21E, S.L.B.&M.**  
**1802' FSL 2149' FEL**



**Uintah Engineering & Land Surveying**  
 85 South 200 East Vernal, Utah 84078  
 (435) 789-1017 \* FAX (435) 789-1813


**TOPOGRAPHIC**  
**MAP**

**12 15 06**  
 MONTH DAY YEAR

**SCALE: 1" = 2000'** **DRAWN BY: C.P.** **REVISED: 00-00-00**

**B**  
**TOPO**





# LEGEND:

- ⊗ DISPOSAL WELLS
- PRODUCING WELLS
- ⬮ SHUT IN WELLS
- ⊗ WATER WELLS
- ⬮ ABANDONED WELLS
- ⬮ TEMPORARILY ABANDONED



Kerr-McGee Oil & Gas Onshore LP

STATE #1021-32J  
SECTION 32, T10S, R21E, S.L.B.&M.  
1802' FSL 2149' FEL



Uintah Engineering & Land Surveying  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813


TOPOGRAPHIC  
MAP

12 15 06  
MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: C.P. REVISED: 00-00-00







APPROXIMATE TOTAL 4" PIPELINE DISTANCE = 880' +/-

APPROXIMATE TOTAL 4" PIPELINE DISTANCE = 833' +/-

# LEGEND:

- PROPOSED ACCESS ROAD
- EXISTING PIPELINE
- PROPOSED PIPELINE
- PROPOSED PIPELINE (SERVICING OTHER WELLS)



Kerr-McGee Oil & Gas Onshore LP

STATE #1021-32J

SECTION 32, T10S, R21E, S.L.B.&M.

1802' FSL 2149' FEL



Uintah Engineering & Land Surveying  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813

TOPOGRAPHIC  
MAP

12 15 06  
MONTH DAY YEAR

SCALE: 1" = 1000' DRAWN BY: C.P. REVISED: 00-00-00





# Kerr-McGee Oil & Gas Onshore LP

STATE #1021-32J

PIPELINE ALIGNMENT

LOCATED IN UINTAH COUNTY, UTAH

SECTION 32, T10S, R21E, S.L.B.&M.



PHOTO: VIEW FROM TIE-IN POINT

CAMERA ANGLE: SOUTHERLY



PHOTO: VIEW OF PIPELINE ALIGNMENT

CAMERA ANGLE: NORTHEASTERLY



- Since 1964 -

**UELS** Uintah Engineering & Land Surveying  
85 South 200 East Vernal, Utah 84078  
435-789-1017 uels@uelsinc.com

PIPELINE PHOTOS

12 15 06  
MONTH DAY YEAR


PHOTO

TAKEN BY: L.K. DRAWN BY: C.P. REVISED: 00-00-00

# Kerr-McGee Oil & Gas Onshore LP

FIGURE #1

LOCATION LAYOUT FOR  
STATE #1021-32J  
SECTION 32, T10S, R21E, S.L.B.&M.  
1802' FSL 2149' FEL  
Install CMP  
as Needed



SCALE: 1" = 50'  
DATE: 12-18-06  
Drawn By: P.M.

Proposed Access Road

Approx. Toe of Fill Slope

F-2.0'  
El. 310.7'

Sta. 3+50



COTTONWOOD WASH  
DO NOT DISTURB

NOTE:  
Flare Pit is to be located  
a min. of 100' from the  
Well Head.

Approx. Top of Cut Slope

CONSTRUCT DIVERSION DITCH

Reserve Pit Backfill  
& Spoils Stockpile

FLARE PIT

C-2.6'  
El. 315.3'

El. 319.8'  
C-17.1'  
(btm. pit)

CONSTRUCT DIVERSION DITCH

15' WIDE BENCH

RESERVE PITS  
(10' Deep)  
Total Pit Capacity  
W/2' of Freeboard  
= 9,850 Bbls. ±  
Total Pit Volume  
= 2,780 Cu. Yds.

Sta. 0+25

El. 318.4'  
C-15.7'  
(btm. pit)

15' WIDE BENCH

Reserve Pit Backfill  
& Spoils Stockpile

NOTES:

Elev. Ungraded Ground At Loc. Stake = 5313.2'  
FINISHED GRADE ELEV. AT LOC. STAKE = 5312.7'

C-9.8'  
El. 322.5'

C-4.7'  
El. 317.4'

Round Corner  
as Needed

Existing Drainage

Existing Drainage

PIPE TUBS

CATWALK

PIPE RACKS

C-0.5'  
El. 313.2'

Sta. 1+50

F-0.4'  
El. 312.3'

TOILET

TRAILER

WATER TANK

LIGHT PLANT

BOILER

COMPRESSOR

BOOSTER

PUMP HOUSE

TRASH

PROPANE STORAGE

C-2.3'  
El. 315.0'

C-1.6'  
El. 314.3'

Sta. 0+00

C-2.5'  
El. 315.2'

Topsoil Stockpile

Topsoil Stockpile

Proposed Access Road  
for the #1021-320

UINTAH ENGINEERING & LAND SURVEYING  
85 So. 200 East \* Vernal, Utah 84078 \* (435) 789-1017

# Kerr-McGee Oil & Gas Onshore LP

FIGURE #2

## TYPICAL CROSS SECTIONS FOR


STATE #1021-32J

SECTION 32, T10S, R21E, S.L.B.&M.

1802' FSL 2149' FEL

1" = 20'  
X-Section  
Scale  
1" = 50'

DATE: 12-18-06  
Drawn By: P.M.



### NOTE:

Topsoil should not be Stripped Below Finished Grade on Substructure Area.

### \* NOTE:

FILL QUANTITY INCLUDES 5% FOR COMPACTION

### APPROXIMATE YARDAGES

#### CUT

(6") Topsoil Stripping = 1,730 Cu. Yds.

Remaining Location = 7,670 Cu. Yds.

TOTAL CUT = 9,400 CU.YDS.

FILL = 1,590 CU.YDS.

EXCESS MATERIAL = 7,810 Cu. Yds.

Topsoil & Pit Backfill = 3,120 Cu. Yds.  
(1/2 Pit Vol.)

EXCESS UNBALANCE = 4,690 Cu. Yds.  
(After Interim Rehabilitation)

UINTAH ENGINEERING & LAND SURVEYING

85 So. 200 East \* Vernal, Utah 84078 \* (435) 789-1017

**WORKSHEET**  
**APPLICATION FOR PERMIT TO DRILL**

APD RECEIVED: 03/16/2007

API NO. ASSIGNED: 43-047-39133

WELL NAME: STATE 1021-32J

OPERATOR: KERR-MCGEE OIL & GAS ( N2995 )

CONTACT: SHEILA UPCHEGO

PHONE NUMBER: 435-781-7024

**PROPOSED LOCATION:**

NWSE 32 100S 210E

SURFACE: 1802 FSL 2149 FEL

BOTTOM: 1802 FSL 2149 FEL

COUNTY: Uintah

LATITUDE: 39.90164 LONGITUDE: -109.5730

UTM SURF EASTINGS: 621992 NORTHINGS: 4417605

FIELD NAME: NATURAL BUTTES ( 630 )

INSPECT LOCATN BY: / /		
Tech Review	Initials	Date
Engineering	DRD	4/24/07
Geology		
Surface		

LEASE TYPE: 3 - State

LEASE NUMBER: ML-21577

SURFACE OWNER: 3 - State

PROPOSED FORMATION: WSMVD

COALBED METHANE WELL? NO

**RECEIVED AND/OR REVIEWED:**

☒ Plat  
☒ Bond: Fed[] Ind[] Sta[] Fee[]  
(No. 22013542 )  
☒ Potash (Y/N)  
☒ Oil Shale 190-5 (B) or 190-3 or 190-13  
☒ Water Permit  
(No. 43-8496 )  
☒ RDCC Review (Y/N)  
(Date: )  
☒ Fee Surf Agreement (Y/N)  
☒ Intent to Commingle (Y/N)

**LOCATION AND SITING:**

\_\_\_ R649-2-3.  
Unit: \_\_\_\_\_  
\_\_\_ R649-3-2. General  
Siting: 460 From Qtr/Qtr & 920' Between Wells  
☒ R649-3-3. Exception  
\_\_\_ Drilling Unit  
Board Cause No: \_\_\_\_\_  
Eff Date: \_\_\_\_\_  
Siting: \_\_\_\_\_  
\_\_\_ R649-3-11. Directional Drill

COMMENTS:

*Needs Permit (04-04-07)*

STIPULATIONS:

*1- Spacing Strip  
2- STATEMENT OF BASIS  
3- OIL SHALE  
4- Surface Csg Cont Strip*





# Application for Permit to Drill

## Statement of Basis

4/16/2007

Utah Division of Oil, Gas and Mining

Page 1

<b>APD No</b>	<b>API WellNo</b>	<b>Status</b>	<b>Well Type</b>	<b>Surf Ownr</b>	<b>CBM</b>
333	43-047-39133-00-00		GW	S	No
<b>Operator</b>	KERR-MCGEE OIL & GAS ONSHORE, LP		<b>Surface Owner-APD</b>		
<b>Well Name</b>	STATE 1021-32J		<b>Unit</b>		
<b>Field</b>	UNDESIGNATED		<b>Type of Work</b>		
<b>Location</b>	NWSE 32 10S 21E S 1802 FSL 2149 FEL GPS Coord (UTM) 621992E 4417605N				

### Geologic Statement of Basis

Kerr McGee proposes to set 1,800' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 4,300'. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the center of Section 32. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water.

Production casing cement should be brought up above the base of the moderately saline ground water to isolate it from fresher waters uphole.

Brad Hill  
APD Evaluator

4/16/2007  
Date / Time

### Surface Statement of Basis

The general area is within the Love area of the upper Cottonwood Wash Drainage. The area is characterized by rolling hills and benches, which are frequently intersected by somewhat gentle draws, which flow into Cottonwood Wash. The draws are occasionally rimmed with steep side hills, which have exposed sand stone bedrock cliffs along the rims. Cottonwood Wash is an ephemeral drainage, which drains northerly approximately 12 miles to the White River. No seeps, springs or streams exist in the area.

This location is approximately 18 miles southeast of Ouray, Utah and is accessed by the Seep Ridge Road then by existing or planned oil field development roads to within 0.15 miles of the proposed site. New construction will be required from this point.

The proposed location is on the west side of the flat bottom of Cottonwood Wash. The drainage itself is incised and to the east. The reserve pit butts up against a side hill on the west. Two small drainages begin within the north part of the location. Drainage will be diverted around both the north and south sides beginning above the reserve pit

Both the surface and minerals are owned by SITLA. Jim Davis represented SITLA at the pre-site investigation. Mr. Davis had no concerns pertaining to this location. The selected location appears to be the best site for drilling and operating a well in the immediate area.

Floyd Bartlett  
Onsite Evaluator

4/4/2007  
Date / Time

### Conditions of Approval / Application for Permit to Drill

<b>Category</b>	<b>Condition</b>
Pits	A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be properly installed and maintained in the reserve pit.
Surface	Drainages adjacent to the proposed pad shall be diverted around the location.

# ON-SITE PREDRILL EVALUATION

## Utah Division of Oil, Gas and Mining

**Operator** KERR-MCGEE OIL & GAS ONSHORE, LP  
**Well Name** STATE 1021-32J  
**API Number** 43-047-39133-0 **APD No** 333 **Field/Unit** UNDESIGNATED  
**Location:** 1/4,1/4 NWSE **Sec** 32 **Tw** 10S **Rng** 21E 1802 FSL 2149 FEL  
**GPS Coord (UTM)** 621994 4417608 **Surface Owner**

### Participants

Floyd Bartlett (DOGM), Jim Davis (SITLA), Carroll Estes, Tony Keznic, and Clay Einerson (Kerr McGee), David Kay (Uintah Engineering and Land Surveying), and Ben Williams (UDWR)

### Regional/Local Setting & Topography

The general area is within the Love area of the upper Cottonwood Wash Drainage. The area is characterized by rolling hills and benches, which are frequently intersected by somewhat gentle draws, which flow into Cottonwood Wash. The draws are occasionally rimmed with steep side hills, which have exposed sand stone bedrock cliffs along the rims. Cottonwood Wash is an ephemeral drainage, which drains northerly approximately 12 miles to the White River. No seeps, springs or streams exist in the area.

This location is approximately 18 miles southeast of Ouray, Utah and is accessed by the Seep Ridge Road then by existing or planned oil field development roads to within 0.15 miles of the proposed site. New construction will be required from this point.

The proposed location is on the west side of the flat bottom of Cottonwood Wash. The drainage itself is incised and to the east. The reserve pit butts up against a side hill on the west. Two small drainages begin within the north part of the location. Drainage will be diverted around both the north and south sides beginning above the reserve pit

Both the surface and minerals are owned by SITLA.

### Surface Use Plan

#### **Current Surface Use**

Grazing  
Recreational  
Wildlife Habitat

#### **New Road**

Miles	Well Pad		Src Const Material	Surface Formation
0.15	Width 278	Length 350	Onsite	UNTA

Ancillary Facilities N

### Waste Management Plan Adequate? Y

### Environmental Parameters

#### **Affected Floodplains and/or Wetland N**

Location is out of the historic flood plain.

#### **Flora / Fauna**

Antelope, cattle, rabbits, coyotes, and small mammals, birds and raptors.

Vegetation is a greasewood type. Scattered greasewood, Russian thistle, sagebrush and spring annuals are present.

**Soil Type and Characteristics**

Deep sandy loam. No surface rock.

**Erosion Issues** N

**Sedimentation Issues** N

**Site Stability Issues** N

**Drainage Diversion Required** Y

Around both sides of the location.

**Berm Required?** N

**Erosion Sedimentation Control Required?** N

**Paleo Survey Run?** Y    **Paleo Potential Observed?** N    **Cultural Survey Run?** N    **Cultural Resources?**

**Reserve Pit****Site-Specific Factors****Site Ranking**

<b>Distance to Groundwater (feet)</b>	>200	0
<b>Distance to Surface Water (feet)</b>	>1000	0
<b>Dist. Nearest Municipal Well (ft)</b>	>5280	0
<b>Distance to Other Wells (feet)</b>	300 to 1320	10
<b>Native Soil Type</b>	Mod permeability	10
<b>Fluid Type</b>	Fresh Water	5
<b>Drill Cuttings</b>	Normal Rock	0
<b>Annual Precipitation (inches)</b>	<10	0
<b>Affected Populations</b>	<10	0
<b>Presence Nearby Utility Conduits</b>	Not Present	0

**Final Score** 25    1    **Sensitivity Level**

**Characteristics / Requirements**

The proposed reserve pit is 70' x 150' x 10' deep located in a cut on the southwest corner of the location. A 20 mil liner with a felt sub-liner is planned by Kerr McGee.

With the proximity to the bottom of an active drainage, care must be taken to insure the reserve pit is adequately lined and maintained.

**Closed Loop Mud Required?** N    **Liner Required?** Y    **Liner Thickness** 16    **Pit Underlayment Required?** Y

**Other Observations / Comments**

Ben Williams representing the UDWR stated the area is classified as yearlong critical habitat for antelope. He stated that the lack of water not forage is the limiting factor affecting the herd in the area. He recommended no restrictions for antelope. No other wildlife is expected to be significantly affected. He gave Jim Davis of SITLA and Carroll Estes of Kerr McGee a copy of his wildlife evaluation and a UDWR recommended seed mix to be used when re-vegetating the location.


ATV's were used to access the site.

Floyd Bartlett  
Evaluator

4/4/2007  
Date / Time



Casing Schematic



Well name:

2007-04 Kerr McGee State 1021-32J

Operator: Kerr McGee Oil &amp; Gas Onshore L.P.

String type: Surface

Project ID:

43-047-39133

Location: Uintah County, Utah

**Design parameters:****Collapse**

Mud weight: 8.300 ppg  
Design is based on evacuated pipe.

**Minimum design factors:****Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 75 °F  
Bottom hole temperature: 100 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,400 ft

Cement top: 442 ft

**Burst**

Max anticipated surface pressure: 1,584 psi  
Internal gradient: 0.120 psi/ft  
Calculated BHP 1,800 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

Tension is based on buoyed weight.

Neutral point: 1,581 ft

**Non-directional string.****Re subsequent strings:**

Next setting depth: 9,060 ft  
Next mud weight: 11.500 ppg  
Next setting BHP: 5,412 psi  
Fracture mud wt: 19.250 ppg  
Fracture depth: 1,800 ft  
Injection pressure: 1,800 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	1800	9.625	32.30	H-40	ST&C	1800	1800	8.876	795.3
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	776	1370	1.765	1800	2270	1.26	51	254	4.98 J

Prepared Helen Sadik-Macdonald  
by: Div of Oil, Gas & Minerals

Phone: (801) 538-5357  
FAX: (801) 359-3940

Date: April 19, 2007  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 1800 ft, a mud weight of 8.3 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

Well name:

2007-04 Kerr McGee State 1021-32J

Operator:

Kerr McGee Oil &amp; Gas Onshore L.P.

String type:

Production

Project ID:

43-047-39133

Location:

Uintah County, Utah

**Design parameters:****Collapse**

Mud weight: 11.500 ppg

Design is based on evacuated pipe.

**Minimum design factors:****Collapse:**

Design factor 1.125

**Environment:**

H2S considered? No

Surface temperature: 75 °F

Bottom hole temperature: 202 °F

Temperature gradient: 1.40 °F/100ft

Minimum section length: 1,500 ft

**Burst:**

Design factor 1.00

Cement top: Surface

**Burst**

Max anticipated surface pressure:

3,419 psi

Internal gradient:

0.220 psi/ft

Calculated BHP

5,412 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)

8 Round LTC: 1.80 (J)

Buttress: 1.60 (J)

Premium: 1.50 (J)

Body yield: 1.50 (B)

**Non-directional string.**

Tension is based on buoyed weight.

Neutral point: 7,503 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	9060	4.5	11.60	I-80	LT&C	9060	9060	3.875	790.6
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	5412	6360	1.175	5412	7780	1.44	87	212	2.44 J

Prepared by: Helen Sadik-Macdonald  
Div of Oil, Gas & MineralsPhone: (801) 538-5357  
FAX: (801) 359-3940Date: April 19, 2007  
Salt Lake City, Utah**Remarks:**

Collapse is based on a vertical depth of 9060 ft, a mud weight of 11.5 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop &amp; Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER \_\_\_\_\_

2. NAME OF OPERATOR:  
KERR MCGEE OIL AND GAS ONSHORE LP

3. ADDRESS OF OPERATOR:  
1368 SOUTH 1200 EAST VERNAL UT 84078

PHONE NUMBER:  
(435) 781-7003

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 1802' FSL 2149' FEL

COUNTY: UINTAH

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWSE 32 10S 21E

STATE: UTAH

5. LEASE DESIGNATION AND SERIAL NUMBER:  
ML-21577

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:  
STATE 1021-32J

9. API NUMBER:  
43-047-39133

10. FIELD AND POOL, OR WILDCAT:  
NATURAL BUTTES

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

An onsite was conducted on 4/4/07 with the Division of Oil, Gas and Mining Representative and SITLA Representative. It was decided to change the proposed pipeline from two 4" pipelines that were approximately 833' +/- and 880' +/- to, two 4" pipelines approximately 4,800' +/- and 1,150' +/-, a 6" pipeline approximately 7,600' +/-, and a 10" pipeline approximately 3,750' +/-.

Please refer to the attached Topo D.

Accepted by the  
Utah Division of  
Oil, Gas and Mining  
For Record Only

NAME (PLEASE PRINT) Ramey Hoopes

TITLE Land Specialist I

SIGNATURE

DATE 4/18/2007


(This space for State use only)

RECEIVED

APR 23 2007

DIV. OF OIL, GAS & MINING





APPROXIMATE TOTAL 4" PIPELINE DISTANCE = 1,150' +/-

APPROXIMATE TOTAL 10" PIPELINE DISTANCE = 3,750' +/-

APPROXIMATE TOTAL 6" PIPELINE DISTANCE = 7,600' +/-

APPROXIMATE TOTAL 4" PIPELINE DISTANCE = 4,800' +/-

#### LEGEND:

- PROPOSED ACCESS ROAD
- EXISTING PIPELINE
- PROPOSED PIPELINE
- - - - PROPOSED PIPELINE (SERVICING OTHER WELLS)

Kerr-McGee Oil & Gas Onshore LP

STATE #1021-32J

SECTION 32, T10S, R21E, S.L.B.&M.

1802' FSL 2149' FEL



**Uintah Engineering & Land Surveying**  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813



**TOPOGRAPHIC  
MAP**

**12 15 06**  
MONTH DAY YEAR

SCALE: 1"=2000' DRAWN BY: C.P. REVISED: 04-12-07





**From:** Ed Bonner  
**To:** Mason, Diana  
**Date:** 6/22/2007 10:23 AM  
**Subject:** Well Clearance

**CC:** Davis, Jim; Garrison, LaVonne; Hill, Brad; Hunt, Gil

The following wells have been given cultural resources clearance by the Trust Lands Cultural Resources Group:

EOG Resources, Inc

Chapita Wells Unit 1330-32 (API 43 047 39293)  
Chapita Wells Unit 1326-32 (API 43 047 39294)  
Chapita Wells Unit 1327-32 (API 43 047 39295)  
Chapita Wells Unit 1325-32 (API 43 047 39296)  
Chapita Wells Unit 1331-32 (API 43 047 39300)  
Chapita Wells Unit 1328-32 (API 43 047 39301)

Kerr McGee Oil & Gas Onshore LP

NBU 1021-19M (API 43 047 38150)  
NBU 1021-32A (API 43 047 39026)  
NBU 1021-32B (API 43 047 39027)  
NBU 1021-32C (API 43 047 39028)  
NBU 1021-32F (API 43 047 39029)  
NBU 1021-32P (API 43 047 39127)  
NBU 1021-32O (API 43 047 39128)  
NBU 1021-32N (API 43 047 39129)  
NBU 1021-32M (API 43 047 39130)  
NBU 1021-32L (API 43 047 39131)  
NBU 1021-32K (API 43 047 39132)  
NBU 1021-32J (API 43 047 39133)  
NBU 1021-32I (API 43 047 39134)  
NBU 1021-32H (API 43 047 39135)  
NBU 1021-32G (API 43 047 39136)  
NBU 1021-32D (API 43 047 39137)  
NBU 1021-32E (API 43 047 39138)

Parallel Petroleum Corporation

Trail Creek Anticline 1-2-6-25 (API 43 047 38324)

QEP Uinta Basin Inc

GB 7SG-36-8-21 (API 43 047 38765)

If you have any questions regarding this matter please give me a call.



JON M. HUNTSMAN, JR.  
Governor

GARY R. HERBERT  
Lieutenant Governor

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
Executive Director

### Division of Oil Gas and Mining

JOHN R. BAZA  
Division Director

June 25, 2007

Kerr-McGee Oil & Gas Onshore, LP  
1368 South 1200 East  
Vernal, UT 84078

Re: State 1021-32J Well, 1802' FSL, 2149' FEL, NW SE, Sec. 32, T. 10 South, R. 21 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

Appropriate information has been submitted to DOGM and administrative approval of the requested exception location is hereby granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-39133.

Sincerely,

Gil Hunt  
Associate Director

er  
Enclosures

cc: Uintah County Assessor  
SITLA



**Operator:** Kerr-McGee Oil & Gas Onshore, LP  
**Well Name & Number** State 1021-32J  
**API Number:** 43-047-39133  
**Lease:** ML 21577

**Location:** NW SE      **Sec.** 32      **T.** 10 South      **R.** 21 East

### **Conditions of Approval**

#### **1. General**

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

#### **2. Notification Requirements**

The operator is required to notify the Division of Oil, Gas and Mining of the following action during drilling of this well:

- 24 hours prior to cementing or testing casing – contact Dan Jarvis
- 24 hours prior to testing blowout prevention equipment – contact Dan Jarvis
- 24 hours prior to spudding the well – contact Carol Daniels
- Within 24 hours of any emergency changes made to the approved drilling program – contact Dustin Doucet
- Prior to commencing operations to plug and abandon the well – contact Dan Jarvis

The operator is required to get approval from the Division of Oil, Gas and Mining before performing any of the following actions during the drilling of this well:

- Plugging and abandonment or significant plug back of this well – contact Dustin Doucet
- Any changes to the approved drilling plan – contact Dustin Doucet

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at:      (801) 538-5338 office      (801) 942-0873 home
- Carol Daniels at:      (801) 538-5284 office
- Dustin Doucet at:      (801) 538-5281 office      (801) 733-0983 home

#### **3. Reporting Requirements**

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.



4. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations, you are required to immediately suspend all operations and immediately inform the Trust Lands Administration and the Division of State History of the discovery of such remains.
5. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)
6. In accordance with Order in Cause No. 190-5(b) dated October 28, 1982, the Operator shall comply with requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operator shall ensure that the surface and/or production casing is properly cemented over the entire oil shale interval as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the Division.
7. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.
8. Surface casing shall be cemented to the surface.

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-21577
2. NAME OF OPERATOR: Kerr-McGee Oil & Gas Onshore, LP		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: NA
3. ADDRESS OF OPERATOR: PO Box 173779 CITY Denver STATE CO ZIP 80217-3779		7. UNIT or CA AGREEMENT NAME: State 1021-32J
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1802 FSL & 2149 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWSE 32 10S 21E		8. WELL NAME and NUMBER: State 1021-32J
PHONE NUMBER: (720) 929-6171		9. API NUMBER: 4304739133
COUNTY: Uintah		10. FIELD AND POOL, OR WILDCAT: Natural Buttes Field
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>APD Extension</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc

Kerr McGee Oil and Gas Onshore, LP respectfully requests a one year extension for State 1021-32J, in order to complete drilling operations. The Utah Division of Oil, Gas, and Mining initially approved this APD on 6/25/2007.

Approved by the  
Utah Division of  
Oil, Gas and Mining

COPY SENT TO OPERATOR

Date: 7.9.2008

Initials: KS

Date: 07-08-08

By: [Signature]

NAME (PLEASE PRINT) <u>Victoria Marques</u>	TITLE <u>Regulatory Intern</u>
SIGNATURE <u>Victoria Marques</u>	DATE <u>6/25/2008</u>

(This space for State use only)

RECEIVED  
JUN 27 2008  
DIV. OF OIL, GAS & MINING

**Application for Permit to Drill  
Request for Permit Extension  
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

**API:** 4304739133  
**Well Name:** State 1021-32J  
**Location:** NWSE 1802 FSL 2149 FEL Sec. 32 T 10S 21E  
**Company Permit Issued to:** Kerr-McGee Oil & Gas Onshore, LP  
**Date Original Permit Issued:** 6/25/2007

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes ☐ No ☒

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes ☐ No ☒

Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes ☐ No ☒

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes ☐ No ☒

Has the approved source of water for drilling changed? Yes ☐ No ☒

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes ☐ No ☒

Is bonding still in place, which covers this proposed well? Yes ☒ No ☐


Victoria Marques  
Signature

6/25/2008  
Date

**Title:** Regulatory Intern

**Representing:** Kerr-McGee Oil & Gas Onshore, LP

**RECEIVED**  
**JUN 27 2008**  
DIV. OF OIL, GAS & MINING

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>			
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ML-21577			
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>			
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b>			
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> STATE 1021-32J			
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1802 FSL 2149 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWSE Section: 32 Township: 10.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047391330000			
<b>PHONE NUMBER:</b> 720 929-6007 Ext		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES			
<b>COUNTY:</b> UTAH		<b>STATE:</b> UTAH			
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>					
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>				
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: 7/3/2009  <input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:  <input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:  <input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION         </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER         </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input checked="" type="checkbox"/> APD EXTENSION            OTHER:         </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER:
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER:			
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> Kerr-McGee Oil & Gas Onshore, L.P. (Kerr-McGee) respectfully requests an extension to this APD for the maximum time allowed. Please contact the undersigned with any questions and/or comments. Thank you.					
<div style="text-align: right;"> <b>Approved by the Utah Division of Oil, Gas and Mining</b> </div>		<b>Date:</b> June 30, 2009  <b>By:</b> 			
<b>NAME (PLEASE PRINT)</b> Danielle Piernot		<b>PHONE NUMBER</b> 720 929-6156			
<b>SIGNATURE</b> N/A		<b>TITLE</b> Regulatory Analyst			
<b>DATE</b> 6/30/2009					



## The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

### Request for Permit Extension Validation Well Number 43047391330000

**API:** 43047391330000

**Well Name:** STATE 1021-32J

**Location:** 1802 FSL 2149 FEL QTR NWSE SEC 32 TWNP 100S RNG 210E MER S

**Company Permit Issued to:** KERR-MCGEE OIL & GAS ONSHORE, L.P.

**Date Original Permit Issued:** 6/25/2007

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☐ Yes ☒ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

**Approved by the  
Utah Division of  
Oil, Gas and Mining**

**Signature:** Danielle Piernot

**Date:** 6/30/2009

**Title:** Regulatory Analyst **Representing:** KERR-MCGEE OIL & GAS ONSHORE, L.P.

**Date:** June 30, 2009

**By:** 

**RECEIVED** June 30, 2009

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ML-21577
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> STATE 1021-32J
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1802 FSL 2149 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWSE Section: 32 Township: 10.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047391330000
<b>PHONE NUMBER:</b> 720 929-6007 Ext		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES
<b>COUNTY:</b> UTAH		<b>STATE:</b> UTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> <b>ACIDIZE</b>	
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:	<input type="checkbox"/> <b>ALTER CASING</b>	
<input checked="" type="checkbox"/> <b>SPUD REPORT</b> Date of Spud: 2/11/2010	<input type="checkbox"/> <b>CASING REPAIR</b>	
<input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<input type="checkbox"/> <b>CHANGE TO PREVIOUS PLANS</b>	
	<input type="checkbox"/> <b>CHANGE TUBING</b>	
	<input type="checkbox"/> <b>CHANGE WELL STATUS</b>	
	<input type="checkbox"/> <b>COMMINGLE PRODUCING FORMATIONS</b>	
	<input type="checkbox"/> <b>DEEPEN</b>	
	<input type="checkbox"/> <b>FRACTURE TREAT</b>	
	<input type="checkbox"/> <b>OPERATOR CHANGE</b>	
	<input type="checkbox"/> <b>PLUG AND ABANDON</b>	
	<input type="checkbox"/> <b>PRODUCTION START OR RESUME</b>	
	<input type="checkbox"/> <b>RECLAMATION OF WELL SITE</b>	
	<input type="checkbox"/> <b>REPERFORATE CURRENT FORMATION</b>	
	<input type="checkbox"/> <b>SIDETRACK TO REPAIR WELL</b>	
	<input type="checkbox"/> <b>TUBING REPAIR</b>	
	<input type="checkbox"/> <b>VENT OR FLARE</b>	
	<input type="checkbox"/> <b>WATER SHUTOFF</b>	
	<input type="checkbox"/> <b>SI TA STATUS EXTENSION</b>	
	<input type="checkbox"/> <b>WILDCAT WELL DETERMINATION</b>	
	<input type="checkbox"/> <b>OTHER:</b>	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> MIRU PETE MARTIN BUCKET RIG. DRILLED 20" CONDUCTOR HOLE TO 40'. RAN 14" 36.7# SCHEDULE 10 PIPE. CMT W/28 SX READY MIX. SPUD WELL LOCATION ON 2/11/2010 AT 12:00 HRS.		
<b>Accepted by the</b> <b>Utah Division of</b> <b>Oil, Gas and Mining</b> <b>FOR RECORD ONLY</b> February 16, 2010		
<b>NAME (PLEASE PRINT)</b> Andy Lytle	<b>PHONE NUMBER</b> 720 929-6100	<b>TITLE</b> Regulatory Analyst
<b>SIGNATURE</b> N/A	<b>DATE</b> 2/12/2010	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ML-21577
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> STATE 1021-32J
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1802 FSL 2149 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWSE Section: 32 Township: 10.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047391330000
<b>PHONE NUMBER:</b> 720 929-6007 Ext		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES
<b>COUNTY:</b> UTAH		<b>STATE:</b> UTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> <b>ACIDIZE</b>	
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:	<input type="checkbox"/> <b>ALTER CASING</b>	
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:	<input type="checkbox"/> <b>CASING REPAIR</b>	
<input checked="" type="checkbox"/> <b>DRILLING REPORT</b> Report Date: 2/24/2010	<input type="checkbox"/> <b>CHANGE TO PREVIOUS PLANS</b>	
	<input type="checkbox"/> <b>CHANGE TUBING</b>	
	<input type="checkbox"/> <b>CHANGE WELL STATUS</b>	
	<input type="checkbox"/> <b>COMMINGLE PRODUCING FORMATIONS</b>	
	<input type="checkbox"/> <b>DEEPEN</b>	
	<input type="checkbox"/> <b>FRACTURE TREAT</b>	
	<input type="checkbox"/> <b>OPERATOR CHANGE</b>	
	<input type="checkbox"/> <b>PLUG AND ABANDON</b>	
	<input type="checkbox"/> <b>PRODUCTION START OR RESUME</b>	
	<input type="checkbox"/> <b>RECLAMATION OF WELL SITE</b>	
	<input type="checkbox"/> <b>REPERFORATE CURRENT FORMATION</b>	
	<input type="checkbox"/> <b>SIDETRACK TO REPAIR WELL</b>	
	<input type="checkbox"/> <b>TUBING REPAIR</b>	
	<input type="checkbox"/> <b>VENT OR FLARE</b>	
	<input type="checkbox"/> <b>WATER SHUTOFF</b>	
	<input type="checkbox"/> <b>SI TA STATUS EXTENSION</b>	
	<input type="checkbox"/> <b>WILDCAT WELL DETERMINATION</b>	
	<input type="checkbox"/> <b>OTHER</b>	
	OTHER:	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b>		
MIRU PROPETRO AIR RIG ON 2/18/2010. DRILLED 11" SURFACE HOLE TO 1845'. RAN 8 5/8 28# J-55 SURFACE CASING. TEST LINES TO 2000 PSI. PUMP 155 BBLS OF H2O , PUMP 20 BBLS OF GEL WATER. PUMP 130 SX CLASS G HI FILL CMT @ 11.0 PPG, 3.82 YLD. PUMP 170 SX OF 15.8 PPG 1.15 YD, CLASS G PREMIUM LITE TAIL CEMENT. DROP PLUG ON FLY AND DISPLACE W/ 170.5 BBLS OF 8.3 PPG H2O, LOSS CIRC 80 BBLS INTO DISPLACEMENT W/ 300 PSI OF LIFT @ 5 BBLS/MIN. LAND PLUG 1000 PSI AND CHECK FLOAT. FLOAT HELD. PUMP TOP OUT W/ 125 SX OF SAME CMT @ 15.8 PPG, 1.15 YD, 5 GAL/SK CEMENT DOWN BACKSIDE AND STAYED. WORT.		
<div style="text-align: right;"> <b>Accepted by the</b>  <b>Utah Division of</b>  <b>Oil, Gas and Mining</b>  <b>FOR RECORD ONLY</b>          February 25, 2010       </div>		
<b>NAME (PLEASE PRINT)</b> Laura Gianakos		<b>PHONE NUMBER</b> 307 752-1169
<b>SIGNATURE</b> N/A		<b>TITLE</b> Regulatory Affairs Supervisor
<b>DATE</b> 2/24/2010		

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ML-21577
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> STATE 1021-32J
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1802 FSL 2149 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWSE Section: 32 Township: 10.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047391330000
<b>PHONE NUMBER:</b> 720 929-6007 Ext		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES
<b>COUNTY:</b> UTAH		<b>STATE:</b> UTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> <b>ACIDIZE</b>	
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:	<input type="checkbox"/> <b>ALTER CASING</b>	
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:	<input type="checkbox"/> <b>CASING REPAIR</b>	
<input checked="" type="checkbox"/> <b>DRILLING REPORT</b> Report Date: 6/24/2010	<input type="checkbox"/> <b>CHANGE TO PREVIOUS PLANS</b>	
	<input type="checkbox"/> <b>CHANGE TUBING</b>	
	<input type="checkbox"/> <b>CHANGE WELL STATUS</b>	
	<input type="checkbox"/> <b>COMMINGLE PRODUCING FORMATIONS</b>	
	<input type="checkbox"/> <b>DEEPEN</b>	
	<input type="checkbox"/> <b>FRACTURE TREAT</b>	
	<input type="checkbox"/> <b>OPERATOR CHANGE</b>	
	<input type="checkbox"/> <b>PLUG AND ABANDON</b>	
	<input type="checkbox"/> <b>PRODUCTION START OR RESUME</b>	
	<input type="checkbox"/> <b>RECLAMATION OF WELL SITE</b>	
	<input type="checkbox"/> <b>REPERFORATE CURRENT FORMATION</b>	
	<input type="checkbox"/> <b>SIDETRACK TO REPAIR WELL</b>	
	<input type="checkbox"/> <b>TUBING REPAIR</b>	
	<input type="checkbox"/> <b>VENT OR FLARE</b>	
	<input type="checkbox"/> <b>WATER SHUTOFF</b>	
	<input type="checkbox"/> <b>SI TA STATUS EXTENSION</b>	
	<input type="checkbox"/> <b>WILDCAT WELL DETERMINATION</b>	
	<input type="checkbox"/> <b>OTHER</b>	
	OTHER:	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> FINISHED DRILLING FROM 1845' TO 9180' ON JUNE 22, 2010. RAN 4 1/2" 11.6# I-80 PRODUCTION CSG. PUMP 40 BBLS SPACER, LEAD CEMENT W/ 1184 569 SX CLASS G PREM LITE @ 13.3 PPG, 1.66 YD. TAILED CEMENT W/ 1184 SX CLASS G 50/50 POZ MIX @ 14.3 PPG, 1.31 YD. DISPLACED W/ 142 BBLS WATER, BUMPED PLUG @ 3657 PSI, HELD 5 MIN, 12 BBLS LEAD BACK TO SURFACE. EST TOP OF TAIL @ 1223'. RD CEMENTERS AND CLEANED PITS. RELEASED PIONEER RIG #69 ON JUNE 24, 2010 @ 19:00 HRS.		
<div style="text-align: right;"> <b>Accepted by the</b>  <b>Utah Division of</b>  <b>Oil, Gas and Mining</b>  <b>FOR RECORD ONLY</b>          June 28, 2010       </div>		
<b>NAME (PLEASE PRINT)</b> Andy Lytle	<b>PHONE NUMBER</b> 720 929-6100	<b>TITLE</b> Regulatory Analyst
<b>SIGNATURE</b> N/A	<b>DATE</b> 6/25/2010	



<div>STATE OF UTAH</div> <div>DEPARTMENT OF NATURAL RESOURCES</div> <div>DIVISION OF OIL, GAS, AND MINING</div>		<div>FORM 9</div> <div>5.LEASE DESIGNATION AND SERIAL NUMBER: ML-21577</div>	
<div>SUNDRY NOTICES AND REPORTS ON WELLS</div> <div>Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.</div>		<div>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</div> <div>7.UNIT or CA AGREEMENT NAME:</div>	
<div>1. TYPE OF WELL</div> <div>Gas Well</div>		<div>8. WELL NAME and NUMBER:</div> <div>STATE 1021-32J</div>	
<div>2. NAME OF OPERATOR:</div> <div>KERR-MCGEE OIL &amp; GAS ONSHORE, L.P.</div>		<div>9. API NUMBER:</div> <div>43047391330000</div>	
<div>3. ADDRESS OF OPERATOR:</div> <div>P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779</div>		<div>PHONE NUMBER:</div> <div>720 929-6007 Ext</div>	
<div>4. LOCATION OF WELL</div> <div>FOOTAGES AT SURFACE:</div> <div>1802 FSL 2149 FEL</div> <div>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</div> <div>Qtr/Qtr: NWSE Section: 32 Township: 10.0S Range: 21.0E Meridian: S</div>		<div>9. FIELD and POOL or WILDCAT:</div> <div>NATURAL BUTTES</div>	
		<div>COUNTY:</div> <div>UINTAH</div>	
		<div>STATE:</div> <div>UTAH</div>	
<div>11.</div> <div>CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</div>			
<div>TYPE OF SUBMISSION</div>		<div>TYPE OF ACTION</div>	
<div><input type="checkbox"/> NOTICE OF INTENT</div> <div>Approximate date work will start:</div> <div><input type="checkbox"/> SUBSEQUENT REPORT</div> <div>Date of Work Completion:</div> <div><input type="checkbox"/> SPUD REPORT</div> <div>Date of Spud:</div> <div><input checked="" type="checkbox"/> DRILLING REPORT</div> <div>Report Date:</div> <div>7/9/2010</div>		<div><input type="checkbox"/> ACIDIZE</div> <div><input type="checkbox"/> CHANGE TO PREVIOUS PLANS</div> <div><input type="checkbox"/> CHANGE WELL STATUS</div> <div><input type="checkbox"/> DEEPEN</div> <div><input type="checkbox"/> OPERATOR CHANGE</div> <div><input checked="" type="checkbox"/> PRODUCTION START OR RESUME</div> <div><input type="checkbox"/> REPERFORATE CURRENT FORMATION</div> <div><input type="checkbox"/> TUBING REPAIR</div> <div><input type="checkbox"/> WATER SHUTOFF</div> <div><input type="checkbox"/> WILDCAT WELL DETERMINATION</div> <div><input type="checkbox"/> ALTER CASING</div> <div><input type="checkbox"/> CHANGE TUBING</div> <div><input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS</div> <div><input type="checkbox"/> FRACTURE TREAT</div> <div><input type="checkbox"/> PLUG AND ABANDON</div> <div><input type="checkbox"/> RECLAMATION OF WELL SITE</div> <div><input type="checkbox"/> SIDETRACK TO REPAIR WELL</div> <div><input type="checkbox"/> VENT OR FLARE</div> <div><input type="checkbox"/> SI TA STATUS EXTENSION</div> <div><input type="checkbox"/> OTHER</div> <div><input type="checkbox"/> CASING REPAIR</div> <div><input type="checkbox"/> CHANGE WELL NAME</div> <div><input type="checkbox"/> CONVERT WELL TYPE</div> <div><input type="checkbox"/> NEW CONSTRUCTION</div> <div><input type="checkbox"/> PLUG BACK</div> <div><input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION</div> <div><input type="checkbox"/> TEMPORARY ABANDON</div> <div><input type="checkbox"/> WATER DISPOSAL</div> <div><input type="checkbox"/> APD EXTENSION</div> <div>OTHER:</div>	
<div>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</div> <div>THE SUBJECT WELL WAS PLACED ON PRODUCTION ON JULY 9, 2010 AT 9:25 A.M. THE CHRONOLOGICAL WELL HISTORY WILL BE SUBMITTED WITH THE WELL COMPLETION REPORT.</div> <div>Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY</div> <div>July 14, 2010</div>			
<div>NAME (PLEASE PRINT)</div> <div>Andy Lytle</div>		<div>PHONE NUMBER</div> <div>720 929-6100</div>	
<div>SIGNATURE</div> <div>N/A</div>		<div>TITLE</div> <div>Regulatory Analyst</div>	
		<div>DATE</div> <div>7/12/2010</div>	

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐ FORM 8  
(highlight changes)

5. LEASE DESIGNATION AND SERIAL NUMBER:  
**ML 21577**

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT or CA AGREEMENT NAME

8. WELL NAME and NUMBER:  
**STATE 1021-32J**

9. API NUMBER:  
**4304739133**

10. FIELD AND POOL, OR WILDCAT  
**NATURAL BUTTES**

11. QTR/QTR, SECTION, TOWNSHIP, RANGE,  
MERIDIAN:  
**NWSE 32 10S 21E S**

12. COUNTY  
**UINTAH**

13. STATE  
**UTAH**

17. ELEVATIONS (DF, RKB, RT, GL):  
**5313 GL**

## WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL ☐ GAS WELL ☒ DRY ☐ OTHER \_\_\_\_\_

b. TYPE OF WORK: NEW WELL ☒ HORIZ. LATS. ☐ DEEP-EN ☐ RE-ENTRY ☐ DIFF. RESVR. ☐ OTHER \_\_\_\_\_

2. NAME OF OPERATOR:  
**KERR MCGEE OIL & GAS ONSHORE, L.P.**

3. ADDRESS OF OPERATOR: P.O.BOX 173779 CITY **DENVER** STATE **CO** ZIP **80217** PHONE NUMBER: **(720) 929-6100**

4. LOCATION OF WELL (FOOTAGES)  
AT SURFACE: **1802 FSL&2149 FEL NWSE S32,T10SR21E**

*BHL reviewed  
by HSM*

AT TOP PRODUCING INTERVAL REPORTED BELOW:

AT TOTAL DEPTH: **1044 fsl 2107 fel**

14. DATE SPUDDED: **2/11/2010** 15. DATE T.D. REACHED: **6/22/2010** 16. DATE COMPLETED: **7/9/2010**

ABANDONED ☐ READY TO PRODUCE ☒

18. TOTAL DEPTH: MD **9,180**  
TVD **9,177 8**

19. PLUG BACK T.D.: MD **9,124**  
TVD **9,124 2**

20. IF MULTIPLE COMPLETIONS, HOW MANY? \*

21. DEPTH BRIDGE MD  
PLUG SET: TVD

22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each)

**CBL/GR-HDIL/ZDL/CN/GR**

*Comp 2*

23. WAS WELL CORED? NO ☒ YES ☐ (Submit analysis)  
WAS DST RUN? NO ☒ YES ☐ (Submit report)  
DIRECTIONAL SURVEY? NO ☐ YES ☒ (Submit copy)

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
20"	14" STL	36.7#		40		28			
11	8.625 J-55	28#		1,827		425			
7 7/8"	4.5 I-80	11.6#		9,167		1,753			

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2 3/8"	8,561							

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)
(A) MESAVERDE	7,410	9,111		
(B)				
(C)				
(D)				

27. PERFORATION RECORD

INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
7,410 9,111	0.36	111	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
7410 - 9111	PUMP 5,590 BBLs SLICK H2O & 190,545 LBS 30/50 SAND

29. ENCLOSED ATTACHMENTS:

☐ ELECTRICAL/MECHANICAL LOGS ☐ GEOLOGIC REPORT ☐ DST REPORT ☐ DIRECTIONAL SURVEY  
☐ SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION ☐ CORE ANALYSIS ☐ OTHER: \_\_\_\_\_

30. WELL STATUS:

**PROD**

**RECEIVED**

**AUG 16 2010**

## 31. INITIAL PRODUCTION

## INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED: 7/9/2010		TEST DATE: 7/11/2010		HOURS TESTED: 24		TEST PRODUCTION RATES: →	OIL – BBL: 0	GAS – MCF: 1,374	WATER – BBL: 576	PROD. METHOD: FLOWING
CHOKE SIZE: 26/64	TBG. PRESS. 625	CSG. PRESS. 925	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL: 0	GAS – MCF: 1,374	WATER – BBL: 576	INTERVAL STATUS: PROD

## INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

## INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

## INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

## 32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

## 33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof. Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

## 34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
GREEN RIVER	867				
BIRD'S NEST	1,107				
MAHOGANY	1,581				
WASATCH	4,078	6,895			
MESAVERDE	6,895	9,180	TD		

## 35. ADDITIONAL REMARKS (Include plugging procedure)

ATTACHED IS THE CHRONOLOGICAL WELL HISTORY AND FINAL SURVEY.

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) ANDREW LYTLE

TITLE REGULATORY ANALYST

SIGNATURE 

DATE 8-5-2010

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

\* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

\*\* ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

# US ROCKIES REGION

## Operation Summary Report

Well: STATE 1021-32J		Spud Conductor: 2/11/2010		Spud Date: 2/19/2010	
Project: UTAH-UINTAH		Site: STATE 1021-32J		Rig Name No: PIONEER 69/69, PROPETRO/	
Event: DRILLING		Start Date: 6/16/2010		End Date: 6/24/2010	
Active Datum: RKB @5,331.01ft (above Mean Sea Leve		UWI: STATE 1021-32J			

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
2/18/2010	14:00 - 0:00	10.00	DRLSUR	01	A	P		MIRU,DRESS COND,INSTALL AIR BOWL,R/U BOOY LINE, R/U PUMPS,BUILD DITCHES WAIT ON DC,S
2/19/2010	0:00 - 2:30	2.50	DRLSUR	01	B	P		FINISH RIG UP COMP,BOOSTER,DOG HOUSE
	2:30 - 4:30	2.00	DRLSUR	06	A	P		P/U BIT # 1 Q507 SERIAL # 7019011 P/U MUD MTR
	4:30 - 6:30	2.00	DRLSUR	08	B	Z		WAIT ON PUMP PARTS
	6:30 - 12:00	5.50	DRLSUR	02	B	P		SPUD 11" HOLE DRL F/ 44' TO 510'-466'-84' HR,WOB=22,ROT=55,MTR=105,GPM=650,PP-1250 ON 1050 OFF, UP/DWN/ROT=45/45/45=
	12:00 - 12:30	0.50	DRLSUR	10	B	P		SURVEY AT 480'= .9 DEGREE AZI=59.3
	12:30 - 16:30	4.00	DRLSUR	02	B	P		DRL F/ 510' TO 1050'=540'-135' HR, WOB=22,ROT=55,MTR=104,GPM=650,PP=1250 ON/1050/OFF,UP/DWN/ROT=55/55/55
	16:30 - 17:00	0.50	DRLSUR	10	B	P		SURVEY @ 1020' = .4 DEGREE 268.0 AZI
	17:00 - 21:00	4.00	DRLSUR	02	B	P		DRL F/ 1050' TO 1530' = 480'-120' HR,WOB=22,ROT=55,MTR=105,PP=1300/ON-1100 OFFGPM=650
	21:00 - 21:30	0.50	DRLSUR	10	B	P		SURVEY @ 1500'=0.9 DEGREE 173 AZI
	21:30 - 0:00	2.50	DRLSUR	02	B	P		DRL F/ 1530' TO 1770' = 240'-96' HR,WOB=22,ROT=55,MTR=104,GPM=650,PP=1300 ON/1100/OFF UP/DWN/ROT=60/60/60
2/20/2010	0:00 - 1:00	1.00	DRLSUR	02	B	P		0DRL F/ 1770' TO 1845' T.D.=75'-75' HR,WOB=22,ROT=55,MTR=104,PP ON 1300 OFF 1100, GPM=650,UP/DWN/ROT=60/60/60
	1:00 - 2:30	1.50	DRLSUR	05	C	P		CIRC TO LDDS
	2:30 - 5:30	3.00	DRLSUR	06	D	P		LDDS - BHA
	5:30 - 8:30	3.00	DRLSUR	12	C	P		HELD SAFETY MTNG,RUN 41 JOINTS 8 5/8 28# J-55 CSNG SHOE @1813.40 BAFFLE IN THE TOP OF SHOE JOINT @ 1770.15 RELEASE RIG TO THE NBU 1021-32A @ 08:30 2-20-2010
	8:30 - 10:00	1.50	DRLSUR	12	E	P		SAFETY MEETING TEST LINES TO 2000' PSI, PUMP 155 BBLS OF H2O , PUMP 20 BBLS OF GEL WATER. PUMP 130 (88.4 BBLS) SX OF 11#, 3.82 YD, 23 GAL SX HI FILL LEAD CEMENT. PUMP 170 SX (34.8 BBLS) OF 15.8#, 1.15 YD, 5 GAL/SK 2% CALC TAIL CEMENT, DROP PLUG ON FLY AND DISPLACE W/ 170.5 BBLS OF 8.3# H2O, LOSS CIRC 80 BBLS INTO DISPLACEMENT W/ 300 PSI OF LIFT @ 5 BBLS/MIN. LAND PLUG 1000 PSI AND CHECK FLOAT. FLOAT HELD. PUMP 125 SX (25.6 BBLS) OF 4% CALC 15.8# 1.15 YD, 5 GAL/SK CEMENT DOWN BACKSIDE AND STAYED. RIG DOWN CEMENTERS.
6/12/2010	3:30 - 8:00	4.50	MIRU	01	E	P		RDRT TO MOVE
	8:00 - 16:00	8.00	MIRU	01	B	P		FINISH RIGGING DOWN AND MOVING EQUIPMENT TO THE NEW LOCATION. RIGGING UP. 1ST TRUCK AND CRANE ON LOCATION 07:00 TRUCKS LEFT @ 15:00 CRANE LEFT @ 16:00. WE HAD TO WAIT TO RAISE THE SUB AND DERRICK FOR GATEWAY TO INSTALL A REMOTE HYDRAULIC VALVE AS PER PIONEER. THEY DID NOT SHOW UP AND THE SUB WAS RAISED @ 15:30. THE SHORT MOVE WAS CONGESTED AND TRUCKING SLOWED BECAUSE OF WAITING FOR THE ROAD TO CLEAR. 5 WEST ROC TRUCKS AND 1 MOUNTAIN WEST.

**US ROCKIES REGION**  
**Operation Summary Report**

Well: STATE 1021-32J			Spud Conductor: 2/11/2010			Spud Date: 2/19/2010		
Project: UTAH-UINTAH			Site: STATE 1021-32J				Rig Name No: PIONEER 69/69, PROPETRO/	
Event: DRILLING			Start Date: 6/16/2010		End Date: 6/24/2010			
Active Datum: RKB @5,331.01ft (above Mean Sea Leve			UWI: STATE 1021-32J					
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
6/13/2010	16:00 - 21:00	5.00	MIRU	01	B	P		RIG UP THE FLOOR, FINNISH THE GROUND EQUIP. PU THE KELLY
	21:00 - 23:00	2.00	MIRU	14	A	P		NU THE BOP
	23:00 - 0:00	1.00	MIRU	15	A	P		PRESSURE TESTED THE UPPER/LOWER KELLY COCK VALVES, AND FLOOR VALVE TO 250# LOW AND 5000#/HIGH FOR 5/10 MIN.
	0:00 - 3:00	3.00	DRLPRO	15	A	P		ATTEMPTING TO TEST THE BOP PU THE BOP CLEANED THE ADAPTER FLANGE AND RESET THE THE BOP. TEST STILL LEAKED OFF.
	3:00 - 12:30	9.50	DRLPRO	15	A	Z		ATTEMPTED TO TEST PU BOP AND CHANGED THE API RING. CHANGED OUT PIPE RAM RUBBERS. TESTED THE PIPE RAMS. BLIND RAMS, INSIDE BOP, FLOOR VALVE INSIDE VALVES, KILL LINE, CHECK VALVE, CHOKE MANIFOLD VALVES AND SUPER CHOKE TO 250 PSI LOW F/ 5 MIN AND 5000 PSI HIGH FOR 10 MIN.. TESTED THE ANNULAR TO 250 PSI /LOW AND 2500/ HIGH. TESTED THE SURFACE CASING TO 1500 PS/30 MIN.
	12:30 - 13:00	0.50	DRLPRO	14	A	P		INSTALLED THE WEAR BUSHING
	13:00 - 17:00	4.00	DRLPRO	06	A	P		RU UP KIMSEY LD MACHINE. PU THE BHA AND DP TO 1700
	17:00 - 18:00	1.00	DRLPRO	09	A	P		SLIPPED AND CUT 120' OF DRILLING LINE.
	18:00 - 20:00	2.00	DRLPRO	23				PU /TORQUE THE KELLY. INSTALLED ROTATING RUBBER AND HAD A PRE SPUD INSPECTION.
	20:00 - 21:00	1.00	DRLPRO	08	A	Z		HAD TO WORK ON THE ROTARY MOTOR.
6/14/2010	21:00 - 23:00	2.00	DRLPRO	02	F	P		WATER IN THE FUEL AND AN AIR LINE PROBLEM TAGGED CEMENT @ 1747'. DRILLED CEMENT AND FLOAT EQUIPMENT.
	23:00 - 0:00	1.00	DRLPRO	02	B	P		DRILLED F/ 1859' - 1936' W/ 15K WOB MOTOR RPM/126 ROTARY RPM/55 8.5/WT 31/VIS.
	0:00 - 2:00	2.00	DRLPRO	06	H	Z		ATEMPTED TO TAKE A SURVEY JUST OUT OF THE SHOE. NO COMMUNICATION FROM THE TOOL TOH F/ THE MWD.
	2:00 - 5:00	3.00	DRLPRO	22	L	Z		SCIENTIFIC INSTALLED A NEW TOOL. STILL NOT WORKING. PULLED THE TOOL AND RETESTED IT ON THE GROUND (GOOD TEST). REINSTALLED THE TOOL AND HAD NO COMMUNICATION.
	5:00 - 7:00	2.00	DRLPRO	06	H	Z		CHANGED OUT THE ANTENNAE. TESTED OK TIH TO DRILL
	7:00 - 16:00	9.00	DRLPRO	02	B	P		DRILLING 1936' - 2915', 979/9 HR, 108.8'/HR. 18K WOB, ROTARY/55 RPM, MOTOR/131RPM. 120 STKS/454 GPM. OFF BTM/856# ON BTM/1131# DIFF/250-350#. PU/SO/ROT=87/75/84. 5' SLIDE(DUE NORTH) PER 979' 30/VIS, 8.4/WT
	16:00 - 16:30	0.50	DRLPRO	07	A	P		RIG SERVICE
	16:30 - 0:00	7.50	DRLPRO	02	B	P		DRILLING 2915' - 3705', 790/7.5 HR, 105.3'/HR. 18K WOB ROTARY/55 RPM, MOTOR/131RPM. 120 STKS/454 GPM. OFF BTM/1000# ON BTM/1350# DIFF/250-350#. PU/SO/ROT=100/97/90. 5' SLIDE(DUE NORTH) PER 790', 29/VIS, 8.7/WT
	0:00 - 11:30	11.50	DRLPRO	02	B	P		DRILLING 3705' - 4496', 791/11.5 HR, 68.8'/HR. 18K WOB ROTARY/55 RPM, MOTOR/131RPM. 120 STKS/454 GPM. OFF BTM/1650# ON BTM/1900# DIFF/250#. PU/SO/ROT=120/90/106.10' SLIDE(DUE NORTH) PER 791', 30-35/VIS, 8.7-10.5/WT
	11:30 - 13:00	1.50	DRLPRO	06	E	P		MADE A 15 STAND WIPER TRIP. WE PULLED 25-30K OVER IN SEVERAL SPOTS.
6/15/2010	13:00 - 13:30	0.50	DRLPRO	07	A	P		RIG SERVICE

# US ROCKIES REGION

## Operation Summary Report

Well: STATE 1021-32J		Spud Conductor: 2/11/2010		Spud Date: 2/19/2010	
Project: UTAH-UINTAH		Site: STATE 1021-32J		Rig Name No: PIONEER 69/69, PROPETRO/	
Event: DRILLING		Start Date: 6/16/2010		End Date: 6/24/2010	
Active Datum: RKB @5,331.01ft (above Mean Sea Leve		UWI: STATE 1021-32J			

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
6/16/2010	13:30 - 18:00	4.50	DRLPRO	02	B	P		DRILLING 4496' - 4812', 316'/4.5 HR, 70.2'/HR. 20K WOB ROTARY/55 RPM, MOTOR/131RPM. 120 STKS/454 GPM. OFF BTTM/1650# ON BTTM/1900# DIFF/250#. PU/SO/ROT=120/90/106.,35/VIS, 10.6/WT
	18:00 - 18:30	0.50	DRLPRO	03	A	X		HAD TO WORK A TIGHT CONNECTION AND REAM THE HOLE @ 4812'. STARTING RAISING THE MUD WT F/ 10.6 - 11.0
	18:30 - 0:00	5.50	DRLPRO	02	B	P		DRILLING 4812' - 5065', 253'/5.5 HR, 46'/HR. 25K WOB ROTARY/55 RPM, MOTOR/131RPM. 120 STKS/454 GPM. OFF BTTM/1920# ON BTTM/2170# DIFF/250#. PU/SO/ROT=125/90/112.,35/VIS, 11.0/WT
	0:00 - 12:30	12.50	DRLPRO	02	B	P		DRILLING 5065' - 5791', 726'/12.5 HR, 58.1'/HR. 25K WOB ROTARY/55 RPM, MOTOR/131RPM. 120 STKS/454 GPM. OFF BTTM/1980# ON BTTM/2250# DIFF/270#. PU/SO/ROT=137/95/117.,36/VIS, 11.3/WT
	12:30 - 13:00	0.50	DRLPRO	07	A	P		RIG SERVICE
	13:00 - 20:00	7.00	DRLPRO	02	B	P		DRILLING 5791' - 6145', 354'/7 HR, 50.6'/HR. 25K WOB ROTARY/55 RPM, MOTOR/121RPM. 110 STKS/454 GPM. OFF BTTM/1990# ON BTTM/2250# DIFF/260#. PU/SO/ROT=140/100/120.,36/VIS, 11.5/WT
	20:00 - 21:00	1.00	DRLPRO	08	B	Z		CHANGED SWABS AND TIGHTENED A BELT
	21:00 - 0:00	3.00	DRLPRO	02	B	P		DRILLING 6145' - 6234', 89'/7.5 HR, 29.6'/HR. 25K WOB ROTARY/55 RPM, MOTOR/121RPM. 110 STKS/454 GPM. OFF BTTM/1990# ON BTTM/2230# DIFF/240#. BALLING PROBLEMS
	0:00 - 10:00	10.00	DRLPRO	02	B	P		PU/SO/ROT=140/90/126.,36/VIS, 11.5/WT
	10:00 - 11:30	1.50	DRLPRO	08	B	Z		DRILLING 6234' - 6510', 276'/10 HR, 27.6'/HR. 25K WOB ROTARY/55 RPM, MOTOR/121RPM. 110 STKS/416 GPM. OFF BTTM/2000# ON BTTM/2350# DIFF/350#. BALLING PROBLEMS
6/17/2010	11:30 - 16:30	5.00	DRLPRO	02	B	P		PU/SO/ROT=141/100/135.,36/VIS, 11.5/WT
	16:30 - 17:00	0.50	DRLPRO	07	A	P		W/O THE PUMP WE HAD 1 PUMP DOWN FOR REPAIRS AND LOST THROTTLE CONTROL ON THE #2 PUMP
	17:00 - 0:00	7.00	DRLPRO	06	A	P		DRILLING 6510' - 6645', 135'/5 HR, 27'/HR. 25K WOB ROTARY/55 RPM, MOTOR/121RPM. 110 STKS/416 GPM. OFF BTTM/2000# ON BTTM/22350# DIFF/200-350#. BALLING PROBLEMS
	0:00 - 2:00	2.00	DRLPRO	06	A	P		PU/SO/ROT=142/100/136.,36/VIS, 11.7/WT
	2:00 - 5:00	3.00	DRLPRO	06	A	P		RIG SERVICE
	5:00 - 10:00	5.00	DRLPRO	03	E	S		TOH F/ BIT TIGHT FROM 5160' - 4560' AND F/ 3250 - 2200'
	10:00 - 15:30	5.50	DRLPRO	02	B	P		PULLED THE MWD TOOL AND LD THE .29 RPG/1.5 BEND MOTOR. PU .16 RPG/1.5 BEND MOTOR. PU MWD TOOL AND SCRIBE THE ASSEMBLY.
	15:30 - 16:00	0.50	DRLPRO	07	A	P		TIH BREAKING CIRCULATION @ THE CASING SHOE AND 4000'. HIT A BRIDGE @ 3100'.
								HIT ABRIDGE @ 6050 AND HAD TO WASH AND REAM THROUGH VERY STICKY BRIDGES F/ 6050' - 6280'. THEN IT WENT ON TO BOTTOM PRETTY GOOD.
								DRILLING 6645' - 6831', 186'/5.5 HR, 33.8'/HR. 20K WOB ROTARY/55 RPM, MOTOR/67RPM. 110 STKS/416 GPM. OFF BTTM/1935# ON BTTM/2200# DIFF/200-350#. PU/SO/ROT=147/117/132.,40/VIS, 12.2/WT
6/18/2010								RIG SERVICE

**US ROCKIES REGION**  
**Operation Summary Report**

Well: STATE 1021-32J			Spud Conductor: 2/11/2010			Spud Date: 2/19/2010		
Project: UTAH-UINTAH			Site: STATE 1021-32J				Rig Name No: PIONEER 69/69, PROPETRO/	
Event: DRILLING			Start Date: 6/16/2010			End Date: 6/24/2010		
Active Datum: RKB @5,331.01ft (above Mean Sea Leve			UWI: STATE 1021-32J					
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
6/19/2010	16:00 - 0:00	8.00	DRLPRO	02	B	P		DRILLING 6831' - 7051' , 220'/8' HR, 27.5'/HR. 23K WOB ROTARY/55 RPM, MOTOR/67RPM. 110 STKS/416 GPM. OFF BTTM/1950# ON BTTM/2225# DIFF/200-350#. PU/SO/ROT=150/120/140.,40/VIS, 12.3/WT
	0:00 - 6:00	6.00	DRLPRO	02	B	P		DRILLING 7051' - 7272' , 221'/6 HR, 36.8'/HR. 23K WOB ROTARY/55 RPM, MOTOR/67RPM. 110 STKS/416 GPM. OFF BTTM/2100# ON BTTM/2325# DIFF/200-300#. PU/SO/ROT=150/120/140.,40/VIS, 12.3/WT
	6:00 - 13:00	7.00	DRLPRO	02	B	P		DRILLING 7272' - 7525' , 253'/7 HR, 36.1'/HR. 23K WOB ROTARY/55 RPM, MOTOR/67RPM. 110 STKS/416 GPM. OFF BTTM/2170# ON BTTM/2345# DIFF/180-350#. PU/SO/ROT=154/124/146.,40/VIS, 12.3/WT
	13:00 - 13:30	0.50	DRLPRO	07	A	P		RIG SERVICE
	13:30 - 0:00	10.50	DRLPRO	02	B	P		DRILLING 7525' - 7841' , 316'/10.5 HR, 30.1'/HR. 23K WOB ROTARY/55 RPM, MOTOR/67RPM. 110 STKS/416 GPM. OFF BTTM/2250# ON BTTM/2500# DIFF/250-300#. PU/SO/ROT=155/125/150.,42/VIS, 12.5/WT
6/20/2010	0:00 - 6:00	6.00	DRLPRO	02	B	P		DRILLING 7841' - 7999' , 158'/6 HR, 26.3'/HR. 23K WOB ROTARY/55 RPM, MOTOR/67RPM. 110 STKS/416 GPM. OFF BTTM/2250# ON BTTM/2500# DIFF/250-300#. PU/SO/ROT=157/125/152.,41/VIS, 12.5/WT
	6:00 - 15:30	9.50	DRLPRO	02	B	P		DRILLING 7999' - 8284' , 285'/9.5 HR, 30'/HR. 25K WOB ROTARY/55 RPM, MOTOR/67RPM. 110 STKS/416 GPM. OFF BTTM/2250# ON BTTM/2525# DIFF/250-300#. PU/SO/ROT=170/120/158.,48/VIS, 12.4/WT
	15:30 - 16:00	0.50	DRLPRO	07	A	P		RIG SERVICE
	16:00 - 0:00	8.00	DRLPRO	02	B	P		DRILLING 8284' - 8505' , 221'/8 HR, 27.6'/HR. 25K WOB ROTARY/55 RPM, MOTOR/67RPM. 110 STKS/416 GPM. OFF BTTM/2140# ON BTTM/2350# DIFF/210-280#. PU/SO/ROT=175/125/160.,48/VIS, 12.5/WT
	0:00 - 8:00	8.00	DRLPRO	02	B	P		DRILLING 8505' - 8632' , 127'/8 HR, 15.6'/HR. 28K WOB ROTARY/55 RPM, MOTOR/67RPM. 110 STKS/416 GPM. OFF BTTM/2140# ON BTTM/2280# DIFF/140-200#. PU/SO/ROT=177/128/162.,48/VIS, 12.5/WT
6/21/2010	8:00 - 8:30	0.50	DRLPRO	05	F	P		MIX AND PUMP A WEIGHTED PILL
	8:30 - 9:30	1.00	DRLPRO	06	A	P		TFB # 2
	9:30 - 11:30	2.00	DRLPRO	08	A	Z		AN AIR SUPPLY HOSE FOR THE #2 DWK CLUTCH HAD TO BE REPAIRED
	11:30 - 15:30	4.00	DRLPRO	06	A	P		TOH F/ BIT #2 AND LD THE MWD TOOLS
	15:30 - 21:00	5.50	DRLPRO	06	A	P		X/O BITS AND TIH. WE HAD SMALL BRIDGES @ 2900 - 3500'. TAGGED A BRIDGE @ 7102'
	21:00 - 23:00	2.00	DRLPRO	03	E	S		WASHED THROUGH BRIDGES. SECTION F/ 7102' - 7400'
	23:00 - 23:30	0.50	DRLPRO	06	A	P		TIH TO 8500'
	23:30 - 0:00	0.50	DRLPRO	03	E	P		REAMED F/ 8500' - 8580'
	0:00 - 0:30	0.50	DRLPRO	03	E	P		WASHED AND REAMED F/ 8580' - 8632'
	0:30 - 6:00	5.50	DRLPRO	02	B	P		DRILLING 8632' - 8809' , 177'/5.5 HR, 32.2'/HR. 22K WOB ROTARY/55 RPM, MOTOR/67RPM. 110 STKS/416 GPM. OFF BTTM/2439# ON BTTM/2610# DIFF/175 - 250#. PU/SO/ROT=165/150/160.,45/VIS, 12.9/WT

**US ROCKIES REGION**  
**Operation Summary Report**

Well: STATE 1021-32J			Spud Conductor: 2/11/2010			Spud Date: 2/19/2010		
Project: UTAH-UINTAH			Site: STATE 1021-32J			Rig Name No: PIONEER 69/69, PROPETRO/		
Event: DRILLING			Start Date: 6/16/2010			End Date: 6/24/2010		
Active Datum: RKB @5,331.01ft (above Mean Sea Leve			UWI: STATE 1021-32J					
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
6/23/2010	6:00 - 12:00	6.00	DRLPRO	02	B	P		DRILLING 8809' - 9030' ,221'6 HR, 36.8'/HR. 22K WOB ROTARY/55 RPM, MOTOR/67RPM. 110 STKS/416 GPM. OFF BTM/2439# ON BTM/2640# DIFF/175 - 250#. PU/SO/ROT=167/150/162.,45/VIS, 13.0/WT
	12:00 - 12:30	0.50	DRLPRO	07	A	P		RIG SERVICE
	12:30 - 16:30	4.00	DRLPRO	02	B	P		DRILL F/ 9030' TO 9180' TD @ 16:30 6/22/2010 ,( 150' @ 37.5' HR ) WOB 20-22 ,RPM 50 ,MMRPM 67 ,SPM 110 ,GPM 416 ,ON/OFF 2570/2380 ,DIFF 175/250, PU/SO/ROT 177-165-170 ,WT 13 ,VIS 44 ,SPR @ 8895' #1 60-865 #2 60-910
	16:30 - 17:30	1.00	DRLPRO	05	C	P		CIRC F/ SHORT TRIP, PUMP PILL
	17:30 - 21:00	3.50	DRLPRO	06	E	P		SHORT TRIP TO CSG SHOE @ 1813' ,TIGHT @ 6150' ,4786' ,4076' TO 3986' & F/3291' TO 2102' 20K TO 40K DRAG
	21:00 - 22:30	1.50	DRLPRO	09	A	P		FILL PIPE ,SLIP & CUT 125' DRILL LINE
	22:30 - 0:00	1.50	DRLPRO	06	E	P		TIH F/ CASING SHOE
	0:00 - 2:00	2.00	DRLPRO	06	E	P		FINISH TIH ,NO PROBLEMS ,WASH 30' TO BTM 4' FILL
	2:00 - 4:00	2.00	DRLPRO	05	C	P		CIRC BTMS UP ,PUMP PILL DROP SURVEY
	4:00 - 9:00	5.00	DRLPRO	06	B	P		TOOH F/ LOGS ,L/D BIT & MOTOR ,1 TIGHT SPOT @ 6624' 20K DRAG
	9:00 - 15:00	6.00	DRLPRO	11	C	P		SAFETY MEETING W/ BAKER ATLAS ,R/U AND RUN TRIPLE COMBO TO 9179' ,LOG OUT ,R/D LOGGERS
	15:00 - 20:00	5.00	DRLPRO	06	A	P		P/U R/R TRI CONE BIT,BIT SUB TIH, WASH 50' TO BOTTOM 4' FILL
	20:00 - 21:30	1.50	DRLPRO	05	C	P		CIRC & COND F/ LDDP ,SAFETY MEETING W/ KIMZEY & R/U LAY DOWN MACHINE ,PUMP PILL LDDP 5400'
	6/24/2010	21:30 - 0:00	2.50	DRLPRO	06	A	P	
0:00 - 5:00		5.00	DRLPRO	06	A	P		SAFETY MEETING W/ KIMZEY CASING & R/U
5:00 - 5:30		0.50	DRLPRO	12	A	P		RUN 217 JTS 4.5 ,11.6 ,I-80 ,BT&C, CASING ,SHOE @ 9168' ,FLOAT COLLAR @ 9124 , MARKER JT @ 4066'
5:30 - 11:30		6.00	DRLPRO	12	C	P		CIRC F/ CEMENT ,R/D CASERS ,SAFETY MEETING W/ BJ SERVICES & R/D CEMENTERS
11:30 - 12:30		1.00	DRLPRO	05	D	P		CEMENT W/ 40 BBLS PRE FLUSH ,569 SX 13.3# ,1.66 YLD LEAD ,1184 SX 14.3# 1.31 YLD TAIL ,DISPLACE W/ 142 BBLS CLAY TREAT WATER ,FINAL LIFT 3067 PSI, BUMP PLUG @ 3657 PSI ,HELD 5 MIN ,12 BBLS LEAD BACK TO PIT ,EST TOP OF TAIL @ 1223'
12:30 - 15:00		2.50	DRLPRO	12	E	P		R/D CEMENTERS ,INSTALL PACK OFF ASSEMBLY
	15:00 - 16:00	1.00	DRLPRO	12	B	P		NIPPLE DOWN BOP ,CLEAN PITS ,RELEASE RIG @ 19:00 6/24/2010 TO STATE 1021-32H
	16:00 - 19:00	3.00	DRLPRO	14	A	P		



## US ROCKIES REGION

## Operation Summary Report

Well: STATE 1021-32J	Spud Conductor: 2/11/2010	Spud Date: 2/19/2010
Project: UTAH-UINTAH	Site: STATE 1021-32J	Rig Name No: PIONEER 69/69, PROPETRO/
Event: DRILLING	Start Date: 6/16/2010	End Date: 6/24/2010
Active Datum: RKB @5,331.01ft (above Mean Sea Leve		
UWI: STATE 1021-32J		

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	19:00 - 19:00	0.00	DRLPRO					<p>CONDUCTOR CASING: Cond. Depth set: 40 Cement sx used: 0</p> <p>SPUD DATE/TIME: 2/19/2010 0630</p> <p>SURFACE HOLE: Surface From depth:44 Surface To depth: 1,859 Total SURFACE hours: 20.00 Surface Casing size:8 5/8 # of casing joints ran: 41 Casing set MD:1,813.0 # sx of cement:425 Cement blend (ppg):LEAD 11 ,TAIL 15.8 ,TOP OUT 15.8 Cement yield (ft3/sk): LEAD 3.82 ,TAIL 1.15 ,TOP OUT 1.15 # of bbls to surface: Describe cement issues: LOST CIRC 80 BBLS INTO TAIL Describe hole issues:</p> <p>PRODUCTION: Rig Move/Skid start date/time: 6/12/2010 3:30 Rig Move/Skid finish date/time:6/12/2010 21:00 Total MOVE hours: 17.5 Prod Rig Spud date/time: 6/13/2010 21:00 Rig Release date/time: 6/24/2010 19:00 Total SPUD to RR hours:262.0 Planned depth MD 9,125 Planned depth TVD 9,125 Actual MD: 9,180 Actual TVD: 9,177 Open Wells \$: \$764,288 AFE \$: \$730,456 Open wells \$/ft:\$83.26</p> <p>PRODUCTION HOLE: Prod. From depth: 1,859 Prod. To depth:9,180 Total PROD hours: 160.5 Log Depth: 9179 Production Casing size: 4.5,11.6,180 # of casing joints ran: 217 Casing set MD:9,167.7 # sx of cement:569 LEAD 1184 TAIL Cement blend (ppg):13.3 LEAD ,14.3 TAIL Cement yield (ft3/sk): 1.66 LEAD ,1.31 TAIL Est. TOC (Lead &amp; Tail) or 2 Stage : 18' LEAD ,1223' TAIL Describe cement issues: FULL RETURNS ,NO PROBLEMS Describe hole issues: NO PROBLEMS</p> <p>DIRECTIONAL INFO: KOP: Max angle: Departure: Max dogleg MD:</p>

**US ROCKIES REGION**  
**Operation Summary Report**

Well: STATE 1021-32J		Spud Conductor: 2/11/2010	Spud Date: 2/19/2010
Project: UTAH-UINTAH		Site: STATE 1021-32J	Rig Name No: GWS 1/1
Event: COMPLETION		Start Date: 7/1/2010	End Date: 7/7/2010
Active Datum: RKB @5,331.01ft (above Mean Sea Level)		UWI: STATE 1021-32J	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
7/1/2010	6:30 - 6:45	0.25	COMP	48		P		HSM, RIGGING UP, PICKINGUP TBG.
	6:45 - 16:30	9.75	COMP	31	I	P		MIRU, NU BOP, RU FLOOR & TBG EQUIP, TALLY & PU TBG TAGGED FILL @ 9,080', RU POWER SWIVEL TO CLEAN OUT FILL & DEEPEN WELL FOR BTM PERFORATION FROM 9,080' TO 9,140' W/ 289 JTS, (18' BELOW FC), CIRC HOLE CLEAN. RD POWER SWIVEL & LD 29 JTS FINISH POOH IN AM FOR PRESS TEST & FIRST SHOOT. SWI SDFN.
7/2/2010	6:30 - 6:45	0.25	COMP	48		P		HSM, PRESSURE TESTING
	6:45 - 8:30	1.75	COMP	31	I	P		POOH TO PRESSURE TEST & PERF, RD FLOOR, ND BOP, NU FRAC VALVE.
	8:30 - 10:00	1.50	COMP	33	C	P		MIRU B & C QUICK TEST. PRESSURE TEST CASING & BOTH FRAC VALVES TO 7,000 PSI. RDMO B&C QUICK TEST.
	10:00 - 14:30	4.50	COMP	37	B	P		MIRU CUTTERS TO PERFORATE ZONE 1. PU 3 1/8" EXP GNS, 23 GRM, .36 HOLES, 120 DEG PHASING. RIH PERF MESA VERDE @ 9,109'-11' 3SPF 6 HOLES, 8,991'-94' 3SPF 9 HOLES, 8,956'-58' 3SPF 6 HOLES, TOTAL 21 HOLES. POOH W / WIRE LINE. PREP TO FRAC ON TUESDAY. SWI SDFWE.
7/6/2010	6:30 - 6:45	0.25	COMP	48		P		HSM, MAKE SURE SURFACE SAFETY VALVE OPEN.
	6:45 - 8:30	1.75	COMP	36	B	P		[STAGE 1] MIRU FRAC TECH PRIME UP PUMPING LINE & PRESS TEST SURFACE LINES TO 8,000 PSI. WHP= 892 PSI, BRK@ 3,587 PSI @ 7 BPM, ISIP 3,001 PSI, FG .77. PUMP 100 BBLS @ 50 BPM 5,560 PSI, = 100% PERFS OPEN. MP 6,410 PSI MR 55 BPM, AP 5,320 PSI AR 53 BPM, ISIP 2,732 PSI, FG.74. NPI -269 PSI, PMPD 1,558 BBLS SW & 52,634 LBS OF 30/50 SND & 5,000 LBS OF RESIN SND. TOTAL PROP 57,634 LBS.
	8:30 - 10:45	2.25	COMP	36	B	P		[STAGE 2] PU 4 1/2" CBP & 3 1/8 EXP GUNS, 23 GRM, .36" HOLES, 120 DEG PHASING, SET 8K HALI BURTON CBP @ 8,770' & PERF MESA VERDE @ 8,676'-80' 3 SPF, 12 SHOTS, 8,583'-86' 3 SPF, 9 SHOTS, TOTAL 21 HOLES. PERFS DID NOT WANTTO BREAK AFTER 8 TRIES SURGED BACK THEN BROKE AT 5,481 PSI 3.8 BPM SPEAR HEADED 250 GAL 15% ACID.  WHP= 1,167 PSI , BRK @ 5,481 PSI @ 3.8 BPM, ISIP 3,369 PSI , FG .82. PUMP 100 BBLS @ 30 BPM @ 5,835 PSI, = 67% PERFS OPEN. MP 6,223 PSI MR 40 BPM, AP 6,031 PSI, AR 32.2 BPM, ISIP 3,171 PSI, FG .80. NPI -198 PSI, PMPD 1,028 BBLS SW & 16,339 LBS OF 30/50 SND & 5,000 LBS OF RESIN SAND. TOTAL PROP 21,339 LBS.

## US ROCKIES REGION

## Operation Summary Report

Well: STATE 1021-32J		Spud Conductor: 2/11/2010		Spud Date: 2/19/2010	
Project: UTAH-UINTAH		Site: STATE 1021-32J			Rig Name No: GWS 1/1
Event: COMPLETION		Start Date: 7/1/2010		End Date: 7/7/2010	
Active Datum: RKB @5,331.01ft (above Mean Sea Level)			UWI: STATE 1021-32J		

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	10:45 - 12:15	1.50	COMP	36	B	P		[STAGE 3] PU 4 1/2" CBP & 3 1/8 EXP GUNS, 23 GRM, .36" HOLES, 120 DEG PHASING, SET 8K HALI BURTON CBP @ 8,533' & PERF MESA VERDE @ 8,456'-59' 3 SPF, 9 SHOTS, 8,414'-15' 3 SPF, 3 SHOTS, 8,366'-67' 3 SPF, 3 SHOTS, 8,250'-52' 3 SPF, 6 SHOTS, TOTAL 21 HOLES.  WHP= 920 PSI , BRK @ 6,271 PSI @ 4.2 BPM, ISIP 3,440 PSI , FG .84. PUMP 100 BBLS @ 43 BPM @ 5,528 PSI, = 100% PERFS OPEN. MP 6,505 PSI MR 50.8 BPM, AP 5,375 PSI, AR 43.7 BPM, ISIP 2,806 PSI, FG .77. NPI -634 PSI, PMPD 1,007 BBLS SW & 30,794 LBS OF 30/50 SND & 5,000 LBS OF RESIN SAND. TOTAL PROP 35,794 LBS.
	12:15 - 13:45	1.50	COMP	36	B			[STAGE 4] PU 4 1/2" CBP & 3 1/8 EXP GUNS, 23 GRM, .36" HOLES, 90 DEG PHASING, SET 8K HALI BURTON CBP @ 7,840' & PERF MESA VERDE @ 7,738'-40' 4 SPF, 8 SHOTS, 7,648'-50' 4 SPF, 8 SHOTS, 7,615'-17' 4 SPF, 8 SHOTS, TOTAL 24 HOLES.  WHP= 825 PSI , BRK @ 5,876 PSI @ 4.3 BPM, ISIP 2,351 PSI , FG .74. PUMP 100 BBLS @ 51 BPM @ 5,150 PSI, = 100% PERFS OPEN. MP 5,487 PSI MR 51.6 BPM, AP 4,278 PSI, AR 51.1 BPM, ISIP 2,489 PSI, FG .76. NPI 138 PSI, PMPD 1,326 BBLS SW & 49,264 LBS OF 30/50 SND & 5,000 LBS OF RESIN SAND. TOTAL PROP 54,264 LBS
	13:45 - 15:00	1.25	COMP	36	B			[STAGE 5] PU 4 1/2" CBP & 3 1/8 EXP GUNS, 23 GRM, .36" HOLES, 90 DEG PHASING, SET 8K HALI BURTON CBP @ 7,565' & PERF MESA VERDE @ 7,517'-19' 4 SPF, 8 SHOTS, 7,483'-85' 4 SPF, 8 SHOTS, 7,410'-12' 4 SPF, 8 SHOTS, TOTAL 24 HOLES.  WHP= 825 PSI , BRK @ 6,231 PSI @ 4.2 BPM, ISIP 2,860 PSI , FG .82. PUMP 100 BBLS @ 50.5 BPM @ 5,365 PSI, = 100% PERFS OPEN. MP 5,351 PSI MR 51.7 BPM, AP 4,680 PSI, AR 50.9 BPM, ISIP 2,420 PSI, FG .76. NPI -440 PSI, PMPD 671 BBLS SW & 17,514 LBS OF 30/50 SND & 4,000 LBS OF RESIN SAND. TOTAL PROP 21,514 LBS. TOTAL FOR JOB WATER 5,590 BBLS, PROP 190,545#
	15:00 - 18:30	3.50	COMP	36	B			SET 8K KILL PLUG @ 7,360', RD WIRELINE & FRAC TECH, ND FRAC VALVE, NU BOP FOR DRILLOUT IN AM, SWI SDFN.
7/7/2010	6:30 - 6:45	0.25	COMP	48		P		HSM, DRILLING PLUGS & LANDING TBG
	6:45 - 8:30	1.75	COMP	31	I	P		RIH TO 7,330', RU POWER SWIVEL TO DRILL PLUGS.

**US ROCKIES REGION**  
**Operation Summary Report**

Well: STATE 1021-32J		Spud Conductor: 2/11/2010		Spud Date: 2/19/2010	
Project: UTAH-UINTAH		Site: STATE 1021-32J			Rig Name No: GWS 1/1
Event: COMPLETION		Start Date: 7/1/2010		End Date: 7/7/2010	
Active Datum: RKB @5,331.01ft (above Mean Sea Level)			UWI: STATE 1021-32J		

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	8:30 - 17:30	9.00	COMP	44	C	P		<p>SICP 0 PSI, BREAK CIRC CONVENTIONAL W/ T-MAC , PRESS TEST BOPS TOO 3000 PSI, START DRLG PLUGS.</p> <p>C/O 20' SAND, TAG 1ST PLUG @ 7,360' DRL PLUG IN 6 MIN. 700 PSI INCREASE RIH.</p> <p>C/O 15' SAND, TAG 2ND PLUG @ 7,565' DRL PLUG IN 4 MIN. 700 PSI INCREASE RIH.</p> <p>C/O 30' SAND, TAG 3RD PLUG @ 7,840' DRL PLUG IN 4 MIN. 1000 PSI INCREASE RIH.</p> <p>C/O 30' SAND, TAG 4TH PLUG @ 8,533' DRL PLUG IN 5 MIN. 600 PSI INCREASE RIH.</p> <p>C/O 45' SAND, TAG 5TH PLUG @ 8,770' DRL PLUG IN 5 MIN. 800 PSI INCREASE RIH</p> <p>RIH TO PBTD @ 9,140' W/ 289 JTS 2 3/8" J-55 TBG, LD 19 JTS, LAND TBG W/ 270 JTS 2 3/8" J-55 EOT 8,561.05', SN @ 8,558.85'</p> <p>RD FLOOR, ND BOPS, NU WH, DROP BALL TO SHEAR OFF BIT PUMPED 25 BBLS NEVER BUILT ANY PRESSURE.</p> <p>TURN WELL OVER TO FLOW BACK CREW. RD ROAD RIG TO NBU 1021-2L .</p> <p>KB= 18' 4 1/16 HANGER= .83' J-55 TBG 270 JTS 2 3/8 J-55 = 8,540.02' TBG DELIVERED: 299 JTS POBS= 2.20' TBG USED: 270 JTS EOT @ 8,561.05' TBG RETURNED: 29 JTS SN @ 8,558.85'</p> <p>TWTR= 5,590 BBLS SICP: 1,400 TWR= 1300 BBLS FTP: 175 TWLTR= 4,290 BBLS ( FBT // RNI TANK # N-3)</p>
7/8/2010	7:00 -			33	A			<p>7 AM FLBK REPORT: CP 925#, TP 625#, 32/64" CK, 70 BWPH, HVY SAND, - GAS TTL BBLS RECOVERED: 3110 BBLS LEFT TO RECOVER: 2480</p>
7/9/2010	7:00 -			33	A			<p>7 AM FLBK REPORT: CP 1425#, TP 525#, 32/64" CK, 36 BWPH, HEAVY SAND, - GAS TTL BBLS RECOVERED: 4244 BBLS LEFT TO RECOVER: 1346</p>
	9:25 -		PROD	50				<p>WELL TURNED TO SALES @ 0925 HR ON 7/9/2010 - 1600 MCFD, 864 BWPD, CP1400#, FTP 575#, CK 32/64"</p>
7/10/2010	7:00 -			33	A			<p>7 AM FLBK REPORT: CP 1125#, TP 425#, 32/64" CK, 25 BWPH, MED SAND, 1.4 GAS TTL BBLS RECOVERED: 4922 BBLS LEFT TO RECOVER: 668</p>
7/11/2010	7:00 -			33	A			<p>7 AM FLBK REPORT: CP 1050#, TP 475#, 32/64" CK, 24 BWPH, MED SAND, 1.5 GAS TTL BBLS RECOVERED: 5478 BBLS LEFT TO RECOVER: 112</p>

**US ROCKIES REGION**  
**Operation Summary Report**

Well: STATE 1021-32J		Spud Conductor: 2/11/2010		Spud Date: 2/19/2010	
Project: UTAH-UINTAH		Site: STATE 1021-32J		Rig Name No: GWS 1/1	
Event: COMPLETION		Start Date: 7/1/2010		End Date: 7/7/2010	
Active Datum: RKB @5,331.01ft (above Mean Sea Level)		UWI: STATE 1021-32J			

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	7:00 -							WELL IP'D ON 7/11/10- 1374 MCFD, 0 BOPD, 576 BOPD, CP 925#, FTP 625#, CK 26/64", LP 136#, 24 HRS

## 1 General

### 1.1 Customer Information

Company	US ROCKIES REGION
Representative	
Address	

### 1.2 Well Information

Well	STATE 1021-32J	Wellbore No.	OH
Well Name	STATE 1021-32J	Common Name	STATE 1021-32J
Project	UTAH-UINTAH	Site	STATE 1021-32J
Vertical Section Azimuth	165.34 (°)	North Reference	True
Origin N/S	0.0 (ft)	Origin E/W	0.0 (ft)
Spud Date	2/19/2010	UWI	STATE 1021-32J
Active Datum	RKB @5,331.01ft (above Mean Sea Level)		

## 2 Survey Name

### 2.1 Survey Name: Survey #1

Survey Name	Survey #1	Company	APC
Started	2/19/2010	Ended	
Tool Name		Engineer	Anadarko

#### 2.1.1 Tie On Point

MD (ft)	Inc (°)	Azi (°)	TVD (ft)	N/S (ft)	E/W (ft)
14.00	0.00	0.00	14.00	0.00	0.00

#### 2.1.2 Survey Stations

Date	Type	MD (ft)	Inc (°)	Azi (°)	TVD (ft)	N/S (ft)	E/W (ft)	V. Sec (ft)	DLeg (°/100ft)	Build (°/100ft)	Turn (°/100ft)	TFace (°)
2/19/2010	Tie On	14.00	0.00	0.00	14.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2/19/2010	NORMAL	494.00	0.09	54.30	494.00	0.22	0.31	-0.14	0.02	0.02	0.00	54.30
	NORMAL	1,034.00	0.04	268.00	1,034.00	0.46	0.46	-0.33	0.02	-0.01	-27.09	-169.79
	NORMAL	1,514.00	0.09	173.00	1,514.00	0.08	0.34	0.01	0.02	0.01	-19.79	-118.09

### 2.2 Survey Name: Survey #2

Survey Name	Survey #2	Company	SCIENTIFIC
Started	6/14/2010	Ended	
Tool Name	MWD	Engineer	Anadarko

#### 2.2.1 Tie On Point

MD (ft)	Inc (°)	Azi (°)	TVD (ft)	N/S (ft)	E/W (ft)
1,514.00	0.09	173.00	1,514.00	0.08	0.34

## 2.2.2 Survey Stations

Date	Type	MD (ft)	Inc (°)	Azi (°)	TVD (ft)	N/S (ft)	E/W (ft)	V. Sec (ft)	DLeg (°/100ft)	Build (°/100ft)	Turn (°/100ft)	TFace (°)
6/14/2010	Tie On	1,514.00	0.09	173.00	1,514.00	0.08	0.34	0.01	0.02	0.01	-19.79	241.91
6/14/2010	NORMAL	1,874.00	1.21	191.98	1,873.97	-3.92	-0.41	3.69	0.31	0.31	5.27	20.47
	NORMAL	2,190.00	1.47	183.09	2,189.89	-11.23	-1.32	10.53	0.11	0.08	-2.81	316.85
	NORMAL	2,506.01	0.63	187.39	2,505.83	-17.00	-1.77	16.00	0.27	-0.27	1.36	176.79
	NORMAL	2,822.01	1.11	191.04	2,821.80	-21.73	-2.58	20.37	0.15	0.15	1.16	8.41
	NORMAL	3,138.01	1.41	183.76	3,137.72	-28.61	-3.42	26.81	0.11	0.09	-2.30	328.24
	NORMAL	3,453.01	1.25	188.20	3,452.64	-35.88	-4.16	33.66	0.06	-0.05	1.41	149.42
6/15/2010	NORMAL	4,398.01	1.18	143.57	4,397.34	-59.02	-2.45	56.47	0.28	-0.17	-8.83	219.48
	NORMAL	4,718.01	1.31	166.26	4,717.26	-65.22	0.37	63.19	0.16	0.04	7.09	86.76
6/15/2010	NORMAL	3,769.01	1.44	188.30	3,768.55	-43.22	-5.23	40.49	0.06	0.06	0.03	0.76
	NORMAL	4,085.01	1.71	171.22	4,084.43	-51.81	-5.08	48.83	0.17	0.09	-5.41	291.18
6/16/2010	NORMAL	5,043.01	1.47	160.82	5,042.17	-72.77	2.62	71.06	0.06	0.05	-1.67	317.75
	NORMAL	5,351.01	1.77	174.89	5,350.05	-81.24	4.35	79.69	0.16	0.10	4.57	60.15
	NORMAL	5,667.01	1.58	173.07	5,665.91	-90.42	5.31	88.82	0.06	-0.06	-0.58	194.73
	NORMAL	5,978.01	1.91	179.05	5,976.77	-99.86	5.91	98.10	0.12	0.11	1.92	31.90
6/17/2010	NORMAL	6,267.01	1.65	167.00	6,265.63	-108.73	6.93	106.94	0.16	-0.09	-4.17	229.29
	NORMAL	6,578.01	1.70	173.40	6,576.50	-117.67	8.46	115.98	0.06	0.02	2.06	78.25
6/18/2010	NORMAL	6,794.01	1.15	167.19	6,792.43	-122.97	9.31	121.32	0.26	-0.25	-2.87	192.59
6/19/2010	NORMAL	7,118.01	1.37	157.01	7,116.35	-129.71	11.55	128.40	0.10	0.07	-3.14	309.34
	NORMAL	7,397.01	1.58	154.33	7,395.26	-136.24	14.51	135.48	0.08	0.08	-0.96	340.47
	NORMAL	7,745.02	1.72	152.49	7,743.12	-145.20	19.00	145.28	0.04	0.04	-0.53	338.35
6/20/2010	NORMAL	8,067.02	1.83	135.94	8,064.97	-153.18	24.81	154.47	0.16	0.03	-5.14	273.76
	NORMAL	8,378.02	1.67	139.00	8,375.82	-160.17	31.24	162.86	0.06	-0.05	0.98	151.24
6/21/2010	NORMAL	8,569.02	2.02	136.38	8,566.72	-164.71	35.39	168.30	0.19	0.18	-1.37	345.14
6/23/2010	NORMAL	9,110.02	2.35	0.16	9,107.55	-160.52	42.00	165.92	0.75	0.06	-25.18	203.64
	NORMAL	9,180.02	2.35	0.16	9,177.50	-157.65	42.01	163.14	0.00	0.00	0.00	0.00

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>			
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ML-21577			
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>			
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b>			
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> STATE 1021-32J			
<b>4. LOCATION OF WELL FOOTAGES AT SURFACE:</b> 1802 FSL 2149 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWSE Section: 32 Township: 10.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047391330000			
<b>PHONE NUMBER:</b> 720 929-6515 Ext		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES			
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH			
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>					
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>				
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: 6/24/2011  <input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:  <input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:  <input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION         </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input checked="" type="checkbox"/> OTHER         </td> <td style="width: 33%; vertical-align: top;"> <input checked="" type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input checked="" type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION            OTHER: <span style="border: 1px solid black; padding: 2px;">Wellhead Repair</span> </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input checked="" type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input checked="" type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <span style="border: 1px solid black; padding: 2px;">Wellhead Repair</span>
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input checked="" type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input checked="" type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <span style="border: 1px solid black; padding: 2px;">Wellhead Repair</span>			
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b>  The operator requests approval to conduct wellhead repair/re-completion operations on the subject well location. The operator proposes to re-complete the Wasatch formation. The operator also requests authorization to commingle the newly Wasatch and existing Mesaverde formations. Please refer to the attached wellhead repair/re-completion procedures.					
<b>NAME (PLEASE PRINT)</b> Gina Becker		<b>PHONE NUMBER</b> 720 929-6086			
<b>SIGNATURE</b> N/A		<b>TITLE</b> Regulatory Analyst II			
<b>DATE</b> 6/24/2011		<b>DATE:</b> 07/05/2011 <b>By:</b> <u><i>Dan K. Quist</i></u>			

Please Review Attached Conditions of Approval

RECEIVED Jun. 24, 2011





**The Utah Division of Oil, Gas, and Mining**

- State of Utah
- Department of Natural Resources

**Electronic Permitting System - Sundry Notices**

**Sundry Conditions of Approval Well Number 43047391330000**

**Authorization: Board Cause No. 210-05.**

# Greater Natural Buttes Unit



**STATE 1021-32J**

**WELLHEAD CHANGEOUT & RE-COMPLETIONS PROCEDURE**

**DATE:6/3/2011**

**AFE#:**

**API#:4304739133**

**WO#:** (For Wellhead Changeout)

**USER ID:OOT937** (Frac Invoices Only)

**COMPLETIONS ENGINEER:** Zachary Garrity, Denver, CO  
(720)-929-6180 (Office)  
(406)-781-6427 (Cell)

**SIGNATURE:**

**ENGINEERING MANAGER: JEFF DUFRESNE**

**SIGNATURE:**

**REMEMBER SAFETY FIRST!**

**Name:** STATE 1021-32J  
**Location:** NW SE Section 32 T10S R21E  
**LAT:** 39.901597 **LONG:** -109.573636 **COORDINATE:** NAD83 (Surface Location)  
**Uintah County, UT**  
**Date:** 6/3/2011

**ELEVATIONS:** 5313' GL 5331' KB *Frac Registry TVD: 9177*

**TOTAL DEPTH:** 9180' **PBTD:** 9123'  
**SURFACE CASING:** 8 5/8", 28# J-55 ST&C @ 1828'  
**PRODUCTION CASING:** 4 1/2", 11.6#, I-80 LT&C @ 9168'  
 Marker Joint **4042-4050'**

**TUBULAR PROPERTIES:**

	BURST (psi)	COLLAPSE (psi)	DRIFT DIA. (in.)	CAPACITIES	
				(bbl/ft)	(gal/ft)
2 3/8" 4.7# J-55 tbg	7,700	8,100	1.901"	0.00387	0.1624
4 1/2" 11.6# I-80 (See above)	7780	6350	3.875"	0.0155	0.6528
2 3/8" by 4 1/2" Annulus				0.0101	0.4227

**TOPS:**

867' Green River Top  
 1107' Bird's Nest Top  
 1581' Mahogany Top  
 4078' Wasatch Top  
 6895' Mesaverde Top

**BOTTOMS:**

6895' Wasatch Bottom  
 9180' Mesaverde Bottom (TD)

**T.O.C. @ 30'** (Cutters CBL - 6/30/2010)

**GENERAL:**

- A minimum of **12** tanks (cleaned lined 500 bbl) of recycled water will be required. Note: Use biocide in tanks and the water needs to be at least 45°F at pump time.
- All perforation depths are from Bakers Induction-Density-Neutron log dated 6/23/2010
- **4** fracturing stages required for coverage.
- Procedure calls for **5** CBP's (**8000** psi) .
- Calculate open perforations after each breakdown. If less than 60% of the perforations appear to be open, ball out with 15% HCl.
- Pump scale inhibitor at 3 gpt (in pad and until 1.25 ppg ramp up is reached) and 10 gpt in all flushes except the final stage. Remember to pre-load the casing with scale inhibitor for the very first stage with 10 gpt.
- 30/50 mesh Ottawa sand, **Slickwater frac.**
- Maximum surface pressure **6200** psi.

**RECEIVED** Jun. 24, 2011

- Flush volumes are the sum of slick water and acid used during displacement (include scale inhibitor as mentioned above). Stage acid and scale inhibitor if necessary to cover the next perforated interval.
- **Call flush at 0 PPG @ inline densimeters. Slow to 5 bbl/min over last 10-20 bbls of flush. Flush to top perf.**
- **If distance between plug and top perf of previous stage is less than 50', it is considered to be tight spacing - over flush stage by 5 bbls (from top perf)**
- Pump 20/40 mesh **curable resin coated sand** last 5,000# on frac stage 1 and 2,500# on frac stages 2-4
- Tubing Currently Landed @~8561
- Originally completed on 7/6/2010
- **Note: Equipment to have on location:**
  - 2 jts 4-1/2" x 11.6# x 8rd
  - 2 jts 4-1/2" x 11.6" x Butress
  - Butress x 8rd change overs.
  - Elevators for 4-1/2" csg.
  - Tongs for 4-1/2" csg.
  - All Weatherford well head parts needed, with Weatherford hand.

#### **Existing Perforations:**

<b><u>PERFORATIONS</u></b>									
<b><u>Formation</u></b>	<b><u>Zone</u></b>	<b><u>Top</u></b>	<b><u>Btm</u></b>	<b><u>spf</u></b>	<b><u>Shots</u></b>	<b><u>Date</u></b>	<b><u>Reason</u></b>	<b><u>Comments</u></b>	<b><u>Producing</u></b>
MESAVERDE		7410	7412	4	8	07/01/2010	PRODUCTION		Yes
MESAVERDE		7483	7485	4	8	07/01/2010	PRODUCTION		Yes
MESAVERDE		7517	7519	4	8	07/01/2010	PRODUCTION		Yes
MESAVERDE		7615	7617	4	8	07/01/2010	PRODUCTION		Yes
MESAVERDE		7648	7650	4	8	07/01/2010	PRODUCTION		Yes
MESAVERDE		7738	7740	4	8	07/01/2010	PRODUCTION		Yes
MESAVERDE		8250	8252	3	6	07/01/2010	PRODUCTION		Yes
MESAVERDE		8366	8367	3	3	07/01/2010	PRODUCTION		Yes
MESAVERDE		8414	8415	3	3	07/01/2010	PRODUCTION		Yes
MESAVERDE		8456	8459	3	9	07/01/2010	PRODUCTION		Yes
MESAVERDE		8583	8586	3	9	07/01/2010	PRODUCTION		Yes
MESAVERDE		8676	8680	3	12	07/01/2010	PRODUCTION		Yes
MESAVERDE		8956	8958	3	6	07/01/2010	PRODUCTION		Yes
MESAVERDE		8991	8994	3	9	07/01/2010	PRODUCTION		Yes
MESAVERDE		9109	9111	3	6	07/01/2010	PRODUCTION		Yes

#### **Relevant History:**

**7/6/2010** – Original completion (5 stage frac)

**8/31/2010** – Slickline ran to TD and set down at 9080'. Ran broach and set down at 8540'. Came out tubing was clean, dropped and chased titanium spring to bottom.

**5/20/2011** - Slickline ran to TD and set down at 9089'. Ran broach and set down at 8549'. Came out tubing was clean, dropped and chased titanium spring and sand viper plunger to bottom

**H2S History:**

Production Date ▼	Gas (avg mcf/day)	Water (avg bbl/day)	Oil (avg bbl/day)	LGR (bbl/MMcf)	Max H2S - Separator (ppm)
5/31/2011	0.00	0.00	0.00	#NA	5.00
4/30/2011	149.90	10.07	4.90	99.84	2.00
3/31/2011	195.58	15.94	0.58	84.45	60.00
2/28/2011	213.00	21.04	6.50	129.28	2.00
1/31/2011	229.94	23.58	1.13	107.46	2.00
12/31/2010	254.81	25.35	1.58	105.71	3.00
11/30/2010	287.07	31.47	5.27	127.96	23.00

**PROCEDURES:** Prior to initiating back-off or casing cutting activities the UDOGM will be notified. Specifically, Mr. Dave Hackford (435-722-7589) will be called, and if not available, Dan Jarvis (801-538-5338) and or Dustin Doucet (801-538-5281) will be notified. No work will be accomplished prior to notifying the appropriate UDOGM representative.

**STATE 1021-32J – WELLHEAD REPLACEMENT PROCEDURE****PREP-WORK PRIOR TO MIRU:**

1. Dig out down to the 2" surface casing valve or to the valve on the riser off the surface casing.
2. Install a tee with 2 valves, with a pressure gauge and sensor on one valve.
3. Open casing valve and record pressures.
4. Install nipple and steel hose on the other valve, the relief valve. Do not use hammer unions. No impact equipment or tools to be used for any of this installation. Extend hose and hard piping to a downwind location at least 100' from the wellhead. Consider installing a manifold so that vent area could be in two locations approx. 90 degrees apart from the wellhead.
5. Open the relief valve and blow well down to the atmosphere.
6. Make a determination of amount of gas flow, either by installation of a choke nipple, bucket test or other.
7. Shut well in. Observe for rate of build-up by utilizing sensor data. Do not build-up for more than 24 hours. Vent gas through the vent line and leave open to the atmosphere.

**WORKOVER PROCEDURE:**

1. MIRU workover rig.
2. Kill well with 10# brine / KCL (dictated by well pressure ).



3. Remove tree, install double BOP with blind and 2 3/8" pipe rams, with accumulator closing unit and manual back-ups. Function test BOP system.
4. TOOH with 2-3/8", 4.7#, J-55 (or N-80) tubing (currently landed at ~8561'). Visually inspect for scale and consider replacing if needed.
5. If tbg looks ok consider running a gauge ring to 7450' (50' below proposed CBP). Otherwise P/U a mill and C/O to 7450' (50' below proposed CBP).
6. Rig up wireline service. RIH and set CBP @ ~7400'. Dump bail **2 sx** cement on top of plug. POOH and RD wireline service. TIH w/ tubing and seating nipple. Land tubing ±60' above cement. RDMO.
7. Monitor well pressures. If surface casing is dead. MIRU. ND WH and NU BOP. POOH w/ tubing.
8. Pressure test casing to 1000 and 3500 psi for 15 minutes each and to 6200 psi for 30 minutes. As per standard operating procedure install steel blowdown line to reserve pit from 4-1/2" X 8-5/8" annulus with pressure relief valve in line. Pressure relief will be set to release at 500 psig. Lock **OPEN** the Braden head valve. Annulus will be monitored throughout stimulation. If release occurs, stimulation will be shut down. Well conditions will be assessed and actions taken as necessary to secure the well. UDOGM will be notified if a release to the annulus occurs.
9. Depending on conditions at wellsite, continue with either CUT/PATCH Procedure or BACK-OFF Procedure.

#### **CUT/PATCH PROCEDURE:**

1. PU internal casing cutters and RIH. Cut casing at +/- 30' from surface.
2. POOH, LD cutters and casing.
3. PU 7 3/8" overshot with 4 1/2" right hand standard wicker grapple, 1 - 4 3/4" drill collar with 3 1/2" IF threads, pup joint, manual bumper sub, and crossovers. If casing cut is deeper than ±30' utilize >7000 ft-lb torque pipe as needed. Pull a minimum of 10,000# to keep grapple engaged if cement top is high (<~900'). If cement top is low (>~900'), more weight will be required to put casing in neutral. Torque casing string to ±7000 ft-lbs, count number of turns to make-up, and document in the daily report. Ensure that tongs are safely anchored to rig and that all personnel are at a safe working distance from the tongs during torque-up and torque release. After initial make-up, place pipe torque to neutral and mark pipe. Place ±7000 ft-lbs on casing a second time, count turns, then return pipe torque to neutral and count turns. Repeat if torque-up turns do not equal torque release turns. Once torque-in equals torque-out, release overshot, POOH, and lay down.
4. TIH w/ skirted mill and dress off the fish top for approximately 1/2 hour. TOOH.
5. PU & RIH w/ 4 1/2" 10k external casing patch on 4 1/2" P-110 casing. Ensure that sliding sleeve assembly shifts ±3' and casing tags no-go portion of patch. NOTE: Shear pins will shear at 3500 to 4500 lbs.

6. Latch fish, PU to 100,000# tension. RU B&C. Cycle pressure test to 3500 psi.
7. Install slips. Land casing w/ 80,000# tension.
8. Cut-off and dress 4 1/2" casing stub.
9. NU frac valves. Test frac valves to 1000 and 3500 psi for 15 minutes each and to 6200 psi for 30 minutes. As per standard operating procedure install steel blowdown line to reserve pit from 4-1/2" X 8-5/8" annulus with pressure relief valve in line. Pressure relief will be set to release at 500 psig. Lock **OPEN** the Braden head valve. Annulus will be monitored throughout stimulation. If release occurs, stimulation will be shut down. Well conditions will be assessed and actions taken as necessary to secure the well. UDOGM will be notified if a release to the annulus occurs.
10. RDMO. Turn well over to completions ops.

**BACK-OFF PROCEDURE:**

1. PU internal casing cutters and RIH. Cut casing at +/- 6' from surface.
2. POOH, LD cutters and casing.
3. PU 4 1/2" overshot. RIH, latch fish. Pick string weight to neutral.
4. MIRU casing crew and wireline services. RIH and shoot string shot at casing collar @ ± 46'.
5. Back-off casing, POOH.
6. PU new casing joint with buttress threads and entry guide and RIH. Tag casing top. Thread into casing and torque up to ±7000 ft-lbs, count number of additional turns to make-up, and document in the daily report. Ensure that tongs are safely anchored to rig and that all personnel are at a safe working distance from the tongs during torque-up and torque release. After initial make-up, place pipe torque to neutral and mark pipe. Place ±7000 ft-lbs on casing a second time, count turns, then return pipe torque to neutral and count turns. Repeat if torque-up turns do not equal torque release turns. Once torque-in equals torque-out go to step 7.
7. PU 100,000# tension string weight. RU B&C. Cycle pressure test to 3500 psi.
8. Install slips. Land casing w/ 80,000# tension.
9. Cut-off and dress 4 1/2" casing stub.
10. NU frac valves. Test frac valves to 1000 and 3500 psi for 15 minutes each and to 6200 psi for 30 minutes. As per standard operating procedure install steel blowdown line to reserve pit from 4-1/2" X 8-5/8" annulus with pressure relief valve in line. Pressure relief will be set to release at 500 psig. Lock **OPEN** the Braden head valve. Annulus will be monitored throughout stimulation. If release occurs, stimulation will be shut down. Well conditions

will be assessed and actions taken as necessary to secure the well. UDOGM will be notified if a release to the annulus occurs.

11. RDMO. Turn well over to completions ops.

**RECOMPLETE – PROCEDURE: (If using any chemicals for pickling tubing or H2S Scavenging, have MSDS for all chemicals prior to starting work.)**

1. MIRU

2. Perf the following with 3-3/8" gun, 23 gm, 0.36"hole:

Zone	From	To	spf	# of shots
MESAVERDE	7091	7092	3	3
MESAVERDE	7117	7118	3	3
MESAVERDE	7199	7200	4	4
MESAVERDE	7292	7293	4	4
MESAVERDE	7314	7315	4	4
MESAVERDE	7354	7356	3	6

3. Breakdown perfs and establish injection rate (include scale inhibitor in fluid). Spot 250 gals of 15% HCL and let soak 5-10 min. Fracture as outlined in Stage 1 on attached listing. Under-displace to ~7091' and trickle 250gal 15%HCL w/ scale inhibitor in flush.

4. Set 8000 psi CBP at ~6,873'. Perf the following 3-3/8" gun, 23 gm, 0.36"hole:

Zone	From	To	spf	# of shots
WASATCH	6658	6661	3	9
WASATCH	6819	6823	3	12

5. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 2 on attached listing. Under-displace to ~6658' and trickle 250gal 15%HCL w/ scale inhibitor in flush.

6. Set 8000 psi CBP at ~6,422'. Perf the following with 3-3/8" gun, 23 gm, 0.36" hole:

Zone	From	To	spf	# of shots
WASATCH	6321	6324	4	12
WASATCH	6369	6372	4	12

7. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 3 on attached listing. Under-displace to ~6321' and trickle 250gal 15%HCL w/ scale inhibitor in flush.

8. Set 8000 psi CBP at ~4,602'. Perf the following with 3-3/8" gun, 23 gm, 0.36" hole:

Zone	From	To	spf	# of shots
WASATCH	4546	4552	4	24

9. Breakdown perfs and establish injection rate. Fracture as outlined in Stage 4 on attached listing. Under-displace to ~4546' and flush only with recycled water.

10. Set 8000 psi CBP at ~4,496'.

11. ND Frac Valves, NU and Test BOPs.

12. TIH with 3 7/8" bit, pump off sub, SN and tubing.
13. Drill plugs and clean out to PBTD. Shear off bit and land tubing at  $\pm 8561'$  unless indicated otherwise by the well's behavior. The well will be commingled at this time.
14. Clean out well with foam and/or swabbing unit until steady flow has been established from completion.
15. **Leave surface casing valve open.** Monitor and report any flow from surface casing.  
RDMO

**For design questions, please call  
Zachary Garrity, Denver, CO  
(720)-929-6180 (Office)  
(406)-781-6427 (Cell)**

**For field implementation questions, please call  
Jeff Samuels, Vernal, UT  
(435)-781-7046 (Office)**

**NOTES:**

**If using any chemicals for pickling tubing or H<sub>2</sub>S Scavenging, have MSDS for all chemicals prior to starting work**

**Verify that the Braden head valve is locked OPEN.**

Acid Pickling and H2S Procedures (If Required)

**\*\*PROCEDURE FOR PUMPING ACID DOWN TBG**

WHEN FINDING SCALE IN TUBING THAT IS ACID SOLUBLE, ENSURE THAT PLUNGER EQUIPMENT IS REMOVED AND ABLE TO PUMP DOWN TBG. INSTALL A 'T' IN PUMP LINE W/2" VALVE THAT NALCO CAN TIE INTO. HAVE 60 BBL 2% KCL MIXED W/ 10-15 GAL H2S SCAVENGER IN RIG FLAT TANK. (WE USED THE RIG FLAT TANK FOR MIXING CHEMICAL SO WE DIDN'T HAVE THE CHEMICAL IN ALL FLUIDS ON LOCATION, ONLY WHAT WE NEEDED TO PUMP DOWN HOLE)

1. PUMP 5-10 BBL 2% KCL DOWN TBG (NALCO CANNOT PUMP AGAINST PRESSURE)
2. NALCO WILL PUMP 3 DRUMS HCL (31%) INTO PUMP LINE.
3. FLUSH BEHIND ACID WITH 10-15 BBL 2% KCL
4. PUMP 2—30 BBL 2% W/ H2S SCAVENGER DOWN TBG.
5. PUMP REMAINDER OF 2% W/ H2S SCAVENGER DOWN CASING AND SHUT WELL IN FOR MINIMUM OF 2 HRS.
6. OVER DISPLACE DOWN TBG AND CSG TO FLUSH ACID AND SCAVENGER INTO FORMATION
7. MONITOR TUBING FOR FLOW AND CASING FOR H2S NOW AS POOH W/ TUBING.

**\*\* PROCEDURE FOR PUMPING H2S SCAVENGER WITHOUT ACID**

PRIOR TO RIG MOVING ON OR AS RIG PULLS ONTO LOCATION. TEST CASING, TUBING AND SEPARATOR FOR H2S. IF FOUND MAKE SURE THAT PLUNGER SYSTEM IS REMOVED (IT IS POSSIBLE TO PUMP AROUND PLUNGERS BUT SOME WILL HAVE A STANDING VALVE IN SEATING NIPPLE).

1. MIX 10-15 GAL H2S SCAVENGER WITH 60-100 BBL 2% KCL IN RIG FLAT TANK.
2. PUMP 25 BBL MIXTURE DOWN TUBING AND REST DOWN CASING. SHUT WELL IN FOR 2 HOURS.
3. IF WELL HAS PRESSURE AFTER 2 HOURS – RETEST CASING AND TUBING FOR H2S.
4. FLUSH TUBING AND CASING PUSHING H2S SCAVENGER INTO FORMATION.
5. MONITOR TUBING FOR FLOW AND CASING FOR H2S NOW AS POOH W/ TUBING.

\*\* As per APC standard operating procedure, APC foreman will verify ALL volumes pumped and record on APC Volume Report Form



Key Contact information

Completion Engineer

Zachary Garrity: 406-781-6427, 720-929-6180

Production Engineer

Jordan Portillo: 435/781-9785, 435/828-6221

Completion Supervisor Foreman

Jeff Samuels: 435-828-6515, 435-781-7046

Completion Manager

Jeff Dufresne: 720-929-6281, 303-241-8428

Vernal Main Office

435-789-3342

Emergency Contact Information—Call 911

Vernal Regional Hospital Emergency: 435-789-3342

Police: (435) 789-5835

Fire: 435-789-4222



## Fracturing Schedules

Name STATE 1021-32J Recomplete

Slickwater Frac

Copy to new book

 Recomplete? Y  
 Pad? N  
 ACTS? N

 Swabbing Days 0 Enter Number of swabbing days here for recompletes  
 Production Log 0 Enter 1 if running a Production Log  
 DFIT 0 Enter Number of DFITs

Stage	Zone	Md-Ft of Pay	Perfs Top, ft. Bot., ft	SPF	Holes	Rate BPM	Fluid Type	Initial ppg	Final ppg	Fluid	Volume gals	Cum Vol gals	Volume BBLs	Cum Vol BBLs	Fluid % of frac	Sand % of frac	Sand lbs	Cum. Sand lbs	Footage from CBP to Flush	Scale Inhib., gal.
1	MESAVERDE	0.13	7091 7092	3	3	Varied	Pump-in test			Slickwater		0	0	0						
	MESAVERDE	0.18	7117 7118	3	3	0	ISIP and 5 min ISIP			Slickwater										45
	MESAVERDE	1.10	7199 7200	4	4	50	Slickwater Pad			Slickwater	17,918	17,918	427	427	15.0%	0.0%	0	0		54
	MESAVERDE	1.04	7292 7293	4	4	50	Slickwater Ramp	0.25	0.63	Slickwater	33,845	51,763	806	1,232	28.3%	21.4%	14,807	14,807		102
	MESAVERDE	0.00	7314 7315	4	4	50	SW Sweep	0	0	Slickwater	0	51,763	0	1,232		0.0%	0	14,807		0
	MESAVERDE	0.69	7354 7355	3	6	50	Slickwater Ramp	0.63	0.75	Slickwater	33,845	85,608	806	2,038	28.3%	33.6%	23,268	38,076		0
	MESAVERDE	0.00				50	SW Sweep	0	0	Slickwater	5,250	90,858	125	2,163		0.0%	0	38,076		0
	MESAVERDE	0.00				50	Slickwater Ramp	0.25	0.75	Slickwater	3,000	93,858	71	2,235		2.2%	1,500	39,576		0
	MESAVERDE	0.00				50	Slickwater Ramp	0.75	1	Slickwater	33,845	127,703	806	3,041	28.3%	42.8%	29,614	69,190		0
	MESAVERDE	0.00				50	Flush (4-1/2)			Slickwater	4,629	132,332	110	3,151				69,190		45
	MESAVERDE	0.00					ISDP and 5 min ISDP													244
	MESAVERDE	0.00								Sand laden Volume		119,453								
		3.14	# of Perfs/stage		24												38,000	12,113	lbs sand/md-ft	
																	CBP depth	6,873		
2	WASATCH	0.08	6658 6661	3	9	Varied	Pump-in test			Slickwater		0	0	0						
	WASATCH	0.16	6819 6823	3	12	0	ISIP and 5 min ISIP			Slickwater										9
	WASATCH	0.00				50	Slickwater Pad			Slickwater	3,116	3,116	74	74	15.0%	0.0%	0	0		31
	WASATCH	0.00				50	Slickwater Ramp	0.25	1	Slickwater	10,387	13,503	247	322	50.0%	37.3%	6,492	6,492		0
	WASATCH	0.00				50	Slickwater Ramp	1	2	Slickwater	7,271	20,774	173	495	35.0%	62.7%	10,906	17,398		0
	WASATCH	0.00				50	Flush (4-1/2)			Slickwater	4,346	25,120	103	598				17,398		0
	WASATCH	0.00					ISDP and 5 min ISDP			Slickwater										0
	WASATCH	0.00																		0
	WASATCH	0.00																		0
	WASATCH	0.00																		42
	WASATCH	0.00																		82
	WASATCH	0.00								Sand laden Volume		20,774								
		0.24	# of Perfs/stage		21												85,000	71,188	lbs sand/md-ft	
																	CBP depth	6,422		
3	WASATCH	0.25	6321 6324	4	12	Varied	Pump-in test			Slickwater		0	0	0						
	WASATCH	0.09	6369 6372	4	12	0	ISIP and 5 min ISIP			Slickwater										9
	WASATCH	0.00				50	Slickwater Pad			Slickwater	3,154	3,154	75	75	15.0%	0.0%	0	0		32
	WASATCH	0.00				50	Slickwater Ramp	0.25	1	Slickwater	10,512	13,666	250	325	50.0%	37.3%	6,570	6,570		0
	WASATCH	0.00				50	Slickwater Ramp	1	2	Slickwater	7,356	21,024	175	501	35.0%	62.7%	11,038	17,808		0
	WASATCH	0.00				50	Flush (4-1/2)			Slickwater	4,126	25,151	98	599				17,008		0
	WASATCH	0.00					ISDP and 5 min ISDP			Slickwater										0
	WASATCH	0.00																		0
	WASATCH	0.00																		0
	WASATCH	0.00																		30
	WASATCH	0.00																		71
	WASATCH	0.00								Sand laden Volume		21,024								
		0.34	# of Perfs/stage		24												62,000	51,925	lbs sand/md-ft	
																	CBP depth	4,602		
4	WASATCH	1.63	4546 4552	4	24	Varied	Pump-in test			Slickwater		0	0	0						
	WASATCH	0.00				0	ISIP and 5 min ISIP			Slickwater										14
	WASATCH	0.00				50	Slickwater Pad			Slickwater	4,654	4,654	111	111	15.0%	0.0%	0	0		47
	WASATCH	0.00				50	Slickwater Ramp	0.25	1	Slickwater	15,513	20,166	369	480	50.0%	37.3%	9,695	9,695		0
	WASATCH	0.00				50	Slickwater Ramp	1	2	Slickwater	10,859	31,025	259	739	35.0%	62.7%	16,288	25,984		0
	WASATCH	0.00				50	Flush (4-1/2)			Slickwater	2,968	33,993	71	809				25,984		0
	WASATCH	0.00					ISDP and 5 min ISDP			Slickwater										0
	WASATCH	0.00																		0
	WASATCH	0.00																		0
	WASATCH	0.00																		60
	WASATCH	0.00								Sand laden Volume		31,025								
		1.63	# of Perfs/stage		24												19,000	15,913	lbs sand/md-ft	
																	CBP depth	4,496		
Totals		5.36			93	16.2	<< Above pump time (min)				Total Fluid	216,596	gals	5,157	bbls		Total Sand	130,180		
						1.7					5,157	bbls			11.5	tanks			Total Scale Inhib. =	458

 Total Stages 4 stages  
 Last Stage Flush 2,968 gals

## Service Company Supplied Chemicals - Job Totals

Friction Reducer	107	gals @	0.5	GPT
Surfactant	214	gals @	1.0	GPT
Clay Stabilizer	214	gals @	1.0	GPT
15% Hcl	1000	gals @	250	gal/stg
Iron Control for acid	5	gals @	5.0	GPT of acid
Surfactant for acid	1	gals @	1.0	GPT of acid
Corrosion Inhibitor for acid	2	gals @	2.0	GPT of acid

## Third Party Supplied Chemicals Job Totals - Include Pumping Charge if Applicable

Scale Inhibitor	458	gals pumped per schedule above	
Biocide	107	gals @	0.5 GPT

RECEIVED Jun. 24, 2011

STATE 1021-32J DIRECTIONAL SURVEY					
MD	TVD	EW	NS	INC	AZI
0	0	0	0	0	0
1874	1873.9	-4.1	-19.4	1.2	192.0
2190	2189.8	-5.0	-26.7	1.5	183.1
2506	2505.7	-5.5	-32.4	0.6	187.4
2822	2821.7	-6.3	-37.2	1.1	191.0
3138	3137.6	-7.1	-44.1	1.4	183.8
3453	3452.5	-7.9	-51.3	1.3	188.2
3769	3768.4	-8.9	-58.7	1.4	188.3
4085	4084.3	-8.8	-67.3	1.7	171.2
4398	4397.2	-6.2	-74.5	1.2	143.6
4718	4717.1	-3.3	-80.7	1.3	166.3
5043	5042.1	-1.1	-88.2	1.5	160.8
5351	5349.9	0.7	-96.7	1.8	174.9
5667	5665.8	1.6	-105.9	1.6	173.1
5978	5976.7	2.2	-115.3	1.9	179.1
6267	6265.5	3.2	-124.2	1.7	167.0
6578	6576.4	4.8	-133.1	1.7	173.4
6794	6792.3	5.6	-138.4	1.2	167.2
7118	7116.2	7.9	-145.1	1.4	157.0
7397	7395.1	10.8	-151.7	1.6	154.3
7745	7743.0	15.3	-160.6	1.7	152.5
8067	8064.8	21.1	-168.6	1.8	135.9
8378	8375.7	27.6	-175.6	1.7	139.0
8569	8566.6	31.7	-180.1	2.0	136.4
9110	9107.4	38.3	-176.0	2.4	0.2

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ML-21577
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> STATE 1021-32J
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1802 FSL 2149 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWSE Section: 32 Township: 10.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047391330000
<b>PHONE NUMBER:</b> 720 929-6515 Ext		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input checked="" type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 9/4/2011	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input checked="" type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION	
<input type="checkbox"/> DRILLING REPORT Report Date:	OTHER: <input style="width: 100px;" type="text"/>	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> THE OPERATOR HAS PERFORMED A RECOMPLETION ON THE SUBJECT WELL. THE OPERATOR HAS RECOMPLETED THE WASATCH AND MESAVERDE FORMATION. THE OPERATOR HAS COMMINGLED THE NEWLY WASATCH AND MESAVERDE FORMATION WITH THE EXISTING MESAVERDE FORMATION. THE SUBJECT WELL WAS PLACED ON PRODUCTION ON 09/04/2011 AT 2:00 PM. THE CHRONOLOGICAL WELL HISTORY WILL BE SUBMITTED WITH THE WELL COMPLETION REPORT.		
<div style="display: flex; justify-content: space-between;"> <div> <b>NAME (PLEASE PRINT)</b>            Sheila Wopsock         </div> <div> <b>PHONE NUMBER</b>            435 781-7024         </div> <div> <b>TITLE</b>            Regulatory Analyst         </div> </div>		
<div style="display: flex; justify-content: space-between;"> <div> <b>SIGNATURE</b>            N/A         </div> <div> <b>DATE</b>            9/6/2011         </div> </div>		

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐ FORM 8  
(highlight changes)

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> DRY <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML21577
b. TYPE OF WORK: NEW WELL <input type="checkbox"/> HORIZ. LATS. <input type="checkbox"/> DEEP-EN <input type="checkbox"/> RE-ENTRY <input type="checkbox"/> DIFF. RESVR. <input checked="" type="checkbox"/> OTHER RECOMPLETION		6. IF INDIAN, ALLOTTEE OR TRIBE NAME
2. NAME OF OPERATOR: KERR MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME
3. ADDRESS OF OPERATOR: P.O.BOX 173779 CITY DENVER STATE CO ZIP 80217		8. WELL NAME and NUMBER: STATE 1021-32J
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: NWSE 1802 FSL 2149 FEL S32,T10S,R21E  AT TOP PRODUCING INTERVAL REPORTED BELOW:  AT TOTAL DEPTH:		9. API NUMBER: 4304739133
10. FIELD AND POOL, OR WILDCAT NATURAL BUTTES		11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWSE 32 10S 21E S
12. COUNTY UINTAH		13. STATE UTAH

14. DATE SPUDDED: 2/11/2010	15. DATE T.D. REACHED: 6/22/2010	16. DATE COMPLETED: 9/4/2011	ABANDONED <input type="checkbox"/> READY TO PRODUCE <input checked="" type="checkbox"/>	17. ELEVATIONS (DF, RKB, RT, GL): 5313 GL
18. TOTAL DEPTH: MD 9,180 TVD 9,177	19. PLUG BACK T.D.: MD 9,124 TVD 9,121	20. IF MULTIPLE COMPLETIONS, HOW MANY? *		21. DEPTH BRIDGE MD 7,388 PLUG SET: TVD
22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each) CBL/GR-DHIL/ZDL/CN/GR			23. WAS WELL CORED? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit copy)	

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
20"	14" STL	36.7#		40		28			
11"	8 5/8" IJ-55	28#		1,827		425		0	
7 7/8"	4 1/2" I-80	11.6#		9,167		1,753			

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2 3/8"	6,543							

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
(A) WASATCH	4,546	6,823			4,546 6,823	0.36	69	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(B) MESAVERDE	7,091	7,356			7,091 7,356	0.36	24	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(C)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(D)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
4546-7356	PUMP 5,346 BBLS SLICK H2O & 130,716 LBS SAND; 115,428 30/50 OTTAWA; 15,288 20/40 RESIN
	4 STAGES

29. ENCLOSED ATTACHMENTS:

- ☐ ELECTRICAL/MECHANICAL LOGS ☐ GEOLOGIC REPORT ☐ DST REPORT ☐ DIRECTIONAL SURVEY  
☐ SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION ☐ CORE ANALYSIS ☐ OTHER: \_\_\_\_\_

30. WELL STATUS:

RECEIVED PROD

NOV 01 2011



## 31. INITIAL PRODUCTION

## INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED: 9/4/2011	TEST DATE: 9/6/2011	HOURS TESTED: 24	TEST PRODUCTION RATES: →	OIL – BBL: 0	GAS – MCF: 166	WATER – BBL: 300	PROD. METHOD: FLOWING
CHOKE SIZE: 26/64	TBG. PRESS. 134	CSG. PRESS. 888	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS: PROD

## INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

## INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

## INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

## 32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

## 33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

## 34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
				GREEN RIVER	867
				BIRD'S NEST	1,107
				MAHOGANY	1,581
				WASATCH	4,078
				MESAVERDE	6,895

## 35. ADDITIONAL REMARKS (Include plugging procedure)

Attached is the chronological recompletion history and perforation report. New recompletion perms are in the Wasatch 4546-6823 and Mesaverde 7091-7356; existing perms in Mesaverde 7410-9111. Production test info is from new recompletion perms. A CIBP is set @ 7388'. Future plans are to drill out the CIBP and commingle existing perms with new perforations. Casing in the well is as previously reported in the original completion report.

## 36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) JAIME SCHARNOWSKETITLE REGULATORY ANALYST

SIGNATURE



DATE

10/24/2011

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

\* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

\*\* ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

**1 General****1.1 Customer Information**

Company	US ROCKIES REGION
Representative	
Address	

**1.2 Well/Wellbore Information**

Well	STATE 1021-32J	Wellbore No.	OH
Well Name	STATE 1021-32J	Wellbore Name	STATE 1021-32J
Report No.	1	Report Date	8/26/2011
Project	UTAH-UINTAH	Site	STATE 1021-32J
Rig Name/No.	MILES 3/3	Event	RECOMPL/RESEREVEADD
Start Date	8/24/2011	End Date	8/29/2011
Spud Date	2/19/2010	Active Datum	RKB @5,331.01ft (above Mean Sea Level)
UWI	STATE 1021-32J		

**1.3 General**

Contractor	JW WIRELINE	Job Method	PERFORATE	Supervisor	FRANK WINN
Perforated Assembly	PRODUCTION CASING	Conveyed Method	WIRELINE		

**1.4 Initial Conditions**

Fluid Type		Fluid Density	
Surface Press		Estimate Res Press	
TVD Fluid Top		Fluid Head	
Hydrostatic Press		Press Difference	
Balance Cond	NEUTRAL		

**1.5 Summary**

Gross Interval	4,546.0 (ft)-7,356.0 (ft)	Start Date/Time	8/26/2011 12:00AM
No. of Intervals	11	End Date/Time	8/26/2011 12:00AM
Total Shots	93	Net Perforation Interval	26.00 (ft)
Avg Shot Density	3.58 (shot/ft)	Final Surface Pressure	
		Final Press Date	

**2 Intervals****2.1 Perforated Interval**


Date	Formation/ Reservoir	CCL@ (ft)	CCL-T S (ft)	MD Top (ft)	MD Base (ft)	Shot Density (shot/ft)	Misfires/ Add. Shot	Diameter (in)	Carr Type /Carr Manuf	Carr Size (in)	Phasing (°)	Charge Desc /Charge Manufacturer	Charge Weight (gram)	Reason	Misrun
8/26/2011 12:00AM	WASATCH/			4,546.0	4,552.0	4.00		0.360	EXP/	3.375	90.00			23.00	PRODUCTIO N

## 2.1 Perforated Interval (Continued)

Date	Formation/ Reservoir	CCL@ (ft)	CCL-T S (ft)	MD Top (ft)	MD Base (ft)	Shot Density (shot/ft)	Misfires/ Add. Shot	Diameter (in)	Carr Type /Carr Manuf	Carr Size (in)	Phasing (°)	Charge Desc /Charge Manufacturer	Charge Weight (gram)	Reason	Misrun
8/26/2011 12:00AM	WASATCH/			6,321.0	6,324.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
8/26/2011 12:00AM	WASATCH/			6,369.0	6,372.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
8/26/2011 12:00AM	WASATCH/			6,658.0	6,661.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
8/26/2011 12:00AM	WASATCH/			6,819.0	6,823.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
8/26/2011 12:00AM	MESAVERDE/			7,091.0	7,092.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
8/26/2011 12:00AM	MESAVERDE/			7,117.0	7,118.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
8/26/2011 12:00AM	MESAVERDE/			7,199.0	7,200.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
8/26/2011 12:00AM	MESAVERDE/			7,292.0	7,293.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
8/26/2011 12:00AM	MESAVERDE/			7,314.0	7,315.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
8/26/2011 12:00AM	MESAVERDE/			7,354.0	7,356.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	

## 3 Plots

## 3.1 Wellbore Schematic



**US ROCKIES REGION**  
**Operation Summary Report**

Well: STATE 1021-32J			Spud Conductor: 2/11/2010			Spud Date: 2/19/2010			
Project: UTAH-UINTAH			Site: STATE 1021-32J				Rig Name No: MILES 3/3, MILES 3/3		
Event: RECOMPL/RESEREVEADD			Start Date: 8/24/2011				End Date: 8/29/2011		
Active Datum: RKB @5,331.01ft (above Mean Sea Level)				UWI: STATE 1021-32J					
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation	
8/25/2011	13:00 - 16:00	3.00	COMP	30	A	P		ROAD RIG AND EQUIP FROM NBU 1021-32A TO LOCATION. SPOT AND RUSU. SPOT EQUIP. MI AND RU JW EWL. HOOK UP B&C. PRES TEST 4-1/2" CSG AND VALVES-- 1020 PSI AT 3:52 PM, 1006 PSI AT 4:08 (LOST 14 PSI IN 15 MIN). 3508 AT 4:11, 3495 PSI AT 4:26 (LOST 13 PSI IN 15 MIN). 6216 PSI AT 4:30, 6156 PSI AT 5:00 PM (LOST 50 PSI IN 30 MIN). BLEED OFF. RD B&C.	
8/26/2011	7:00 - 7:15	0.25	COMP	48		P		JSA- FRAC AND PERF.	
	7:15 - 8:00	0.75	COMP	37	B	P		PERF STG 1) RIH W/ 3-1/8" GUN (23 GM, .36 HOLE SIZE. 3 SPF ON 120* AND 4 SPF ON 90*) AND PERF MESA VERDE AS PER DESIGN.	

**US ROCKIES REGION**  
**Operation Summary Report**

Well: STATE 1021-32J		Spud Conductor: 2/11/2010	Spud Date: 2/19/2010
Project: UTAH-UINTAH	Site: STATE 1021-32J		Rig Name No: MILES 3/3, MILES 3/3
Event: RECOMPL/RESERVEADD	Start Date: 8/24/2011	End Date: 8/29/2011	
Active Datum: RKB @5,331.01ft (above Mean Sea Level)		UWI: STATE 1021-32J	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	8:00 - 8:00	0.00	COMP	36	B	P		<p>8-10:30 FINISH RU SUPERIOR. PRES TEST LINES TO 7220 PSI. LOST 10 PSI IN 15 MIN.</p> <p>FRAC STG 1) WHP 93 PSI, BRK 3430 PSI @ 4.7 BPM. ISIP 2277 PSI, FG .75. PERF OPEN CALC @ 51.6 BPM @ 5276 PSI = 90% HOLES OPEN. ISIP 2744 PSI, FG .82, NPI 467 PSI. MP 5750 PSI, MR 50.8 BPM, AP 4930 PSI, AR 48.6 BPM, PMP 3259 BBLs SW &amp; 63,590 LBS OF 30/50 Snd &amp; 5451 LBS OF 20/40 RESIN Snd. TOTAL PROP 69,041 LBS. SWI, X-OVER FOR WL.</p> <p>PERF STG 2) PU 4 1/2 8K HAL CBP &amp; 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 120 DEG PHASING. RIH SET CBP @ 6853'. P/U PERF AS PER STG 2 PERF DESIGN. POOH. X-OVER FOR FRAC CREW.</p> <p>FRAC STG 2) WHP 850 PSI, BRK 2973 PSI @ 4.4 BPM. ISIP 2255 PSI, FG .77. PERF OPEN CALC @ 39.5 BPM @ 5110 PSI = 72% HOLES OPEN. ISIP 3696 PSI, FG .99, NPI 1441 PSI. MP 5517 PSI, MR 48.4 BPM, AP 5316 PSI, AR 43.3 BPM, PMP 622 BBLs SW &amp; 14,757 LBS OF 30/50 Snd &amp; 2854 LBS OF 20/40 RESIN Snd. TOTAL PROP 17,611 LBS. SWI, X-OVER FOR WL.</p> <p>PERF STG 3) PU 4 1/2 8K HAL CBP &amp; 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 90 DEG PHASING. RIH SET CBP @ 6402' P/U PERF AS PER STG 3 PERF DESIGN. POOH. X-OVER FOR FRAC.</p> <p>FRAC STG 3) WHP 730 PSI, BRK 5210 PSI @ 4.7 BPM (2 TIMES TO GET BREAK). ISIP 2567 PSI, FG .84. PERF OPEN CALC @ 46.4 BPM @ 5066 PSI = 86% HOLES OPEN. ISIP 2842 PSI, FG .89, NPI 275 PSI. MP 6024 PSI, MR 51.0 BPM, AP 4961 PSI, AR 48.9 BPM, PMP 617 BBLs SW &amp; 15,181 LBS OF 30/50 Snd &amp; 2670 LBS OF 20/40 RESIN Snd. TOTAL PROP 17,851 LBS. SWI, X-OVER FOR WL.</p> <p>PERF STG 4) PU 4 1/2 8K HAL CBP &amp; 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 90 DEG PHASING. RIH SET CBP @ 4582' P/U PERF AS PER STG 3 PERF DESIGN. POOH. X-OVER FOR FRAC.</p> <p>FRAC STG 4) WHP 350 PSI, BRK 1655 PSI @ 3.4 BPM. ISIP 1056 PSI, FG .67. PERF OPEN CALC @ 48.2 BPM @ 4496 PSI = 67% HOLES OPEN. ISIP 2842 PSI, FG .89, NPI 275 PSI. MP 6024 PSI, MR 51.0 BPM, AP 4961 PSI, AR 48.9 BPM, PMP 848 BBLs SW &amp; 21900 LBS OF 30/50 Snd &amp; 4313 LBS OF 20/40 RESIN Snd. TOTAL PROP 26,213 LBS. SWI, X-OVER FOR WL.</p> <p>RIH W/ 4-1/2" HALCO 8K CBP AND SET KILL PLUG</p>

**US ROCKIES REGION**  
**Operation Summary Report**

Well: STATE 1021-32J		Spud Conductor: 2/11/2010		Spud Date: 2/19/2010	
Project: UTAH-UINTAH		Site: STATE 1021-32J			Rig Name No: MILES 3/3, MILES 3/3
Event: RECOMPL/RESEREVEADD		Start Date: 8/24/2011		End Date: 8/29/2011	
Active Datum: RKB @5,331.01ft (above Mean Sea Level)			UWI: STATE 1021-32J		

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
AT 4496'								
RD SUPERIOR AND JW EWL.								
TTL 30/50 115,428#								
TTL 20/40 RESIN 15,288#								
CUM TTL SAND 130,716#								
TTL CL FL 5346 BBL								
SCALE INHIB 424 GAL								
BIOCIDE 112 GAL								
8/29/2011	7:00 - 7:15	0.25	COMP	48		P		JSA- ND/NU. PU TBG. D/O PLUGS.
	7:15 - 9:30	2.25	COMP	30	F	P		SICP 0. ND FRAC VALVES. NU TBG HEAD AND BOP. RU FLOOR AND TBG EQUIP
	9:30 - 11:45	2.25	COMP	31	I	P		MU 3-7/8" MILL, PUMP OPEN BIT SUB, AND 1.87" XN. RIH AS MEAS AND PU 2-3/8" J-55 PROD TBG. TAG AT 4478' W/ 142-JTS IN. RU DRLG EQUIP. FILL TBG AND PRES TEST TO 3000#. GOOD. EST CIRC AND D/O PLUGS.
	11:45 - 18:30	6.75	COMP	44	C	P		#1- C/O 12' SAND TO CBP AT 4482'. MILL OUT IN 16 MIN. 0 INC. FCP 0. RIH. #2- C/O 30' SAND TO CBP AT 4569'. MILL OUT IN 16 MIN. 50 INC. FCP 0. RIH. #3- C/O 30' SAND TO CBP AT 6395'. MILL OUT IN 14 MIN. 0 INC. 0 FCP. RIH. #4- C/O 30' SAND TO CBP AT 7388'. MILL OUT IN 11 MIN. 300 INC. FCP100. RIH. CONFER WITH ZACH GARRITY. LAND AND EVALUATE. CIBP- C/O 20' SAND TO 7376' (CIBP AT 7388') W/ 233-JTS IN. CIRC CLEAN.
RD PWR SWIVEL. POOH AS LD 13-JTS TBG. PU 7" 5K HANGER. LUB IN AND LAND 220-JTS J-55 W/ MILL AT 6983.37'. RD FLOOR. ND BOP. NU WH. PUMP OPEN BIT SUB AT 1300#. NO FLOW OR BLOW FROM SURFACE. SITP 200#. SICP 300#. HOOK UP TO HAL 9000 AND TURN OVER TO FBC AND SALES.								
TBG DETAIL KB 18.00								
7" 5K WFOR HANGER 1.00								
220-JTS 2-3/8" J-55 TBG 6961.31								
3-7/8" MILL, PMP OPEN 3.06								
MILL AT 6983.37								
270-JTS PRODUCTION PULLED								
220-JTS PRODUCTION RAN IN								
50-JTS 2-3/8" J-55 TO B&C								
8/30/2011	7:00 -			33	A			TWTR 5346 / TWR 450 / LTR 4896
								7 AM FLBK REPORT: CP 400#, TP 100#, OPEN/64" CK, 60 BWPH, LIGHT SAND, - GAS
								TTL BBLs RECOVERED: 730
								BBLs LEFT TO RECOVER: 4616



**US ROCKIES REGION**  
**Operation Summary Report**

Well: STATE 1021-32J		Spud Conductor: 2/11/2010		Spud Date: 2/19/2010	
Project: UTAH-UINTAH		Site: STATE 1021-32J			Rig Name No: MILES 3/3, MILES 3/3
Event: RECOMPL/RESEREVEADD		Start Date: 8/24/2011		End Date: 8/29/2011	
Active Datum: RKB @5,331.01ft (above Mean Sea Level)			UWI: STATE 1021-32J		

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
8/31/2011	7:00 -			33	A			7 AM FLBK REPORT: CP 1100#, TP 50#, OPEN/64" CK, 35 BWPH, LIGHT SAND, - GAS TTL BBLS RECOVERED: 1790 BBLS LEFT TO RECOVER: 3556
9/4/2011	7:00 -			33	A			7 AM FLBK REPORT: CP 1100#, TP 150#, OPEN/64" CK, 20 BWPH, LIGHT SAND, - GAS TTL BBLS RECOVERED: 2861 BBLS LEFT TO RECOVER: 2485
9/6/2011	7:00 -			50				WELL IP'D ON 9/6/11 - 166 MCFD, 0 BOPD, 300 BWPD, CP 888#, FTP 134#, CK 26/64", LP 26#, 24 HRS
9/28/2011	11:00 - 12:30	1.50	COMP	30	A	P		ROAD RIG FROM 1021-32G. SPOT AND RUSU. FTP 100, FCP 100, SISCP 0. LAY PMP LINE.
	12:30 - 14:00	1.50	COMP	30	F	P		PMP 10 BBLS DOWN TBG. ND WH. NU BOP. RU FLOOR AND TBG EQUIP. UNLAND TBG. LUB OUT AND LD 7" 5K HANGER.
	14:00 - 16:30	2.50	COMP	31	I	P		RIH FROM 6983'. RIH AS MEAS AND PU 13-JTS TBG TO TAG AT 7361' W/ #233. POOH AS LD 33-JTS AND SB 206-JTS 2-3/8" J-55 TBG. LD MILL AND PMP OPEN SUB.
	16:30 - 17:30	1.00	COMP	31	I	P		MU NOTCHED 1.87" XN AND RIH W/ 62-JTS. EOT AT 1960'. SDFN
9/29/2011	7:00 - 7:15	0.25	COMP	48		P		JSA- RIH W/ PKR. SET PKR. SWAB.
	7:15 - 8:30	1.25	COMP	31	I	P		SITP 600, SICP 600. BWD. PMP 35 BBLS DOWN CSG. PU WCS 4-1/2" PKR. RIH W/ 144-JTS TBG. SET PKR AT 4579' WITH SN AT 6543'.
	8:30 - 11:00	2.50	COMP	46	E	P		WAIT FOR SWAB PARTS
	11:00 - 16:30	5.50	COMP	42	B	P		RU SWAB. IFL AT 2600'. MADE 9 SWAB RUNS, RECOVER 46-1/2 BBLS TO GET WELL TO FLOW. FLOWED 1-1/2 HRS, RECOVER 24-3/4 BBLS FLOWING. TOTAL OF 71-1/4 BBLS CUMM. 4-1/2" CSG PRES TO 80 PSI AFTER 8 HRS SHUT IN. SWMFN.
9/30/2011	7:00 - 7:15	0.25	COMP	48		P		JSA- ND/NU. RDSU.
	7:15 - 9:00	1.75	COMP	30	C	P		SITP 1100, SICP 220. SURFACE OPEN. BLOW TBG DOWN. PMP 15 BBLS DOWN TBG. RD SWAB. RD FLOOR. ND BOP. NU WH. SHUT WELL IN. RDSU AND MOVE OFF. TURN WELL OVER TO PRODUCTION DEPT FOR EVALUATION WITH PKR ISOLATION.
								TBG DETAIL KB 18.00
								7" 5K HANGER 1.00
								5K COMPRESSION -1.00
								144-JTS 2-3/8" J-55 TBG 4558.66
								4-1/2" WCS AS1 6.10
								62-JTS 2-3/8" J-55 1959.49
								NOTCHED 1.87" XN 1.05
								EOT 6543.30
								PKR SET AT 4579.66

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐ FORM 8  
(highlight changes)

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> DRY <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML21577
b. TYPE OF WORK: NEW WELL <input type="checkbox"/> HORIZ. LATS. <input type="checkbox"/> DEEP-EN <input type="checkbox"/> RE-ENTRY <input type="checkbox"/> DIFF. RESVR. <input checked="" type="checkbox"/> OTHER RECOMPLETION		6. IF INDIAN, ALLOTTEE OR TRIBE NAME
2. NAME OF OPERATOR: KERR MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME
3. ADDRESS OF OPERATOR: P.O.BOX 173779 CITY DENVER STATE CO ZIP 80217		8. WELL NAME and NUMBER: STATE 1021-32J
PHONE NUMBER: (720) 929-6100		9. API NUMBER: 4304739133
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: NWSE 1802 FSL 2149 FEL S32,T10S,R21E  AT TOP PRODUCING INTERVAL REPORTED BELOW:  AT TOTAL DEPTH:		10. FIELD AND POOL, OR WILDCAT NATURAL BUTTES
		11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWSE 32 10S 32J S
		12. COUNTY UINTAH
		13. STATE UTAH

14. DATE SPUDDED: 2/11/2010	15. DATE T.D. REACHED: 6/22/2010	16. DATE COMPLETED: 9/4/2011	ABANDONED <input type="checkbox"/> READY TO PRODUCE <input checked="" type="checkbox"/>	17. ELEVATIONS (DF, RKB, RT, GL): 5313 GL
18. TOTAL DEPTH: MD 9,180 TVD 9,177	19. PLUG BACK T.D.: MD 9,124 TVD 9,121	20. IF MULTIPLE COMPLETIONS, HOW MANY? *		21. DEPTH BRIDGE MD 7,388 PLUG SET: TVD
22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each) CBL/GR-DHIL/ZDL/CN/GR			23. WAS WELL CORED? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit copy)	

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
20"	14" STL	36.7#		40		28			
11"	8 5/8" IJ-55	28#		1,827		425		0	
7 7/8"	4 1/2" I-80	11.6#		9,167		1,753			

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2 3/8"	6,543							

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
(A) WASATCH	4,546	6,823			4,546 6,823	0.36	69	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(B) MESAVERDE	7,091	7,356			7,091 7,356	0.36	24	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(C)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(D)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

27. PERFORATION RECORD

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
4546-7356	PUMP 5,346 BBLS SLICK H2O & 130,716 LBS SAND; 115,428 30/50 OTTAWA; 15,288 20/40 RESIN
	4 STAGES

29. ENCLOSED ATTACHMENTS:

- |   |  |                                       |   |
|---|--|---------------------------------------|---|
| <input type="checkbox"/> ELECTRICAL/MECHANICAL LOGS                         | <input type="checkbox"/> GEOLOGIC REPORT | <input type="checkbox"/> DST REPORT   | <input type="checkbox"/> DIRECTIONAL SURVEY |
| <input type="checkbox"/> SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION | <input type="checkbox"/> CORE ANALYSIS   | <input type="checkbox"/> OTHER: _____ |   |

30. WELL STATUS:

PROD

## 31. INITIAL PRODUCTION

## INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED: 9/4/2011		TEST DATE: 9/6/2011		HOURS TESTED: 24		TEST PRODUCTION RATES: →	OIL – BBL: 0	GAS – MCF: 166	WATER – BBL: 300	PROD. METHOD: FLOWING
CHOKE SIZE: 26/64	TBG. PRESS. 134	CSG. PRESS. 888	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL: 0	GAS – MCF: 166	WATER – BBL: 300	INTERVAL STATUS: PROD

## INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

## INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

## INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

## 32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

## 33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

## 34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
				GREEN RIVER	867
				BIRD'S NEST	1,107
				MAHOGANY	1,581
				WASATCH	4,078
				MESAVERDE	6,895

## 35. ADDITIONAL REMARKS (Include plugging procedure)

Attached is the chronological recompletion history and perforation report. New recompletion perfs are in the Wasatch 4546-6823 and Mesaverde 7091-7356'; existing perfs in Mesaverde 7410-9111. Production test info is from new recompletion perfs. A CIBP is set @ 7388'. Future plans are to drill out the CIBP and commingle existing perfs with new perforations. Casing in the well is as previously reported in the original completion report.

## 36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) JAIME SCHARNOWSKETITLE REGULATORY ANALYST

SIGNATURE

DATE 10/24/2011

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

\* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

\*\* ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>			
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ML-21577			
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>			
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b>			
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> STATE 1021-32J			
<b>4. LOCATION OF WELL FOOTAGES AT SURFACE:</b> 1802 FSL 2149 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWSE Section: 32 Township: 10.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047391330000			
<b>PHONE NUMBER:</b> 720 929-6515 Ext		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES			
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH			
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>					
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>				
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: 11/9/2011  <input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:  <input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:  <input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input checked="" type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION         </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER         </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION            OTHER: <input style="width: 100px;" type="text"/> </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input checked="" type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input checked="" type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>			
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b>  The Operator requests approval to workover the subject well. Workover operations consist of water shutoff by perforation squeeze. Please see the attached procedure. Thank you.					
<b>NAME (PLEASE PRINT)</b> Jaime Scharnowske		<b>PHONE NUMBER</b> 720 929-6304			
<b>SIGNATURE</b> N/A		<b>TITLE</b> Regulatory Analyst			
<b>DATE</b> 11/9/2011					

**Name:** STATE 1021-32J  
**Location:** NW SE Section 32 T10S R21E  
**LAT:** 39.9014897 **LONG:** -109.5734927 **COORDINATE:** NAD83 (Surface Location)  
**Uintah County, UT**  
**Date:** 11/8/2011

**WASATCH ABANDONMENT**

**ELEVATIONS:** 5313' GL 5331' KB *Frac Registry TVD: 9177*

**TOTAL DEPTH:** 9180' **PBTD:** 9123'  
**SURFACE CASING:** 8 5/8", 28# J-55 ST&C @ 1828'  
**PRODUCTION CASING:** 4 1/2", 11.6#, I-80 LT&C @ 9167'  
 Marker Joint **4042-4050'**

**TUBULAR PROPERTIES:**

	BURST (psi)	COLLAPSE (psi)	DRIFT DIA. (in.)	CAPACITIES	
				(bbl/ft)	(gal/ft)
2 3/8" 4.7# J-55 tbg	7,700	8,100	1.901"	0.00387	0.1624
4 1/2" 11.6# I-80 (See above)	7780	6350	3.875"	0.0155	0.6528
2 3/8" by 4 1/2" Annulus				0.0101	0.4227

**TOPS:**

867' Green River Top  
 1107' Bird's Nest Top  
 1581' Mahogany Top  
 4078' Wasatch Top  
 6895' Mesaverde Top

**BOTTOMS:**

6895' Wasatch Bottom  
 9180' Mesaverde Bottom (TD)

**Relevant History:**

**7/6/2010** – Original completion (5 stage frac)

**8/31/2010** – Slickline ran to TD and set down at 9080'. Ran broach and set down at 8540'. Came out tubing was clean, dropped and chased titanium spring to bottom.

**5/20/2011** - Slickline ran to TD and set down at 9089'. Ran broach and set down at 8549'. Came out tubing was clean, dropped and chased titanium spring and sand viper plunger to bottom

**9/4/2011** – Recomplete Wasatch and top MV. IP 160 mcf/day 100 BBL+ H2O/day.

**9/29/2011** – Isolate suspected wet perms - SITP 600, SICP 600. BWD. PMP 35 BBLs DOWN CSG. PU WCS 4-1/2" PKR. RIH W/ 144-JTS TBG. SET PKR AT 4579' WITH SN AT 6543'.

**Symptoms:**

- High LGR. Water shut-off needed to increase production.

**Procedure Outline:**

- MIRU. N/D WH. N/U BOP. Release packer @ 4579'. unland tubing and TOOH.
- With Wireline, RIH w/ gauge ring and junk basket to ~6900'. RIH W/ 4-1/2" CBP set same @ ~6850'. POOH. RIH w/ 4-1/2" CICR on tubing and set same @ ~6625'. Sting into CICR and establish injection rate.
- R/U cement company and pump recommended cement job into perforations from 6658'- 6823', based off injection rate and pressure. PUH w/ stinger and cap CICR with cement. Reverse circulate clean. TOOH.
- RIH w/ 4-1/2" CICR on tubing and set same @ ~6300'. Sting into CICR and establish injection rate.
- R/U cement company and pump recommended cement job into perforations from 6321'- 6372', based off injection rate and pressure. PUH w/ stinger and cap CICR with cement. Reverse circulate clean. TOOH.
- RIH w/ 4-1/2" CICR on tubing and set same @ ~4520'. Sting into CICR and establish injection rate.
- R/U cement company and establish injection rate into perms 4546'-4552'. Pump recommended cement job into perforations from 4546'-4552', based off injection rate and pressure. PUH w/ stinger and cap CICR with cement. Reverse circulate clean.
- Apply appropriate pressure and WOC.
- POOH. RIH w/ 3-7/8" w/mill. D-O Cement retainer's and CBP, replace mill when necessary. Test each interval for 10 min and 1,000 psi, contact engineer if squeezes don't test. CO to PBTD~ 9123'.
- TOOH remove mill. Land tubing at +/- 8300'. Be careful not to over-torque any collars. Broach tubing.
- N/D BOP. N/U WH. RDMO. RTP



**Recomplete Perforations**

Legal Well Name	Date	MD Top (usft)	MD Base (usft)	Shot Density (shot/ft)
<b>SET CEMENT RETAINER 4520'</b>				
STATE 1021-32J	8/26/2011	4,546	4,552	4
<b>SET CEMENT RETAINER 6300'</b>				
STATE 1021-32J	8/26/2011	6,321	6,324	4
STATE 1021-32J	8/26/2011	6,369	6,372	4
<b>SET CEMENT RETAINER 6625'</b>				
STATE 1021-32J	8/26/2011	6,658	6,661	3
STATE 1021-32J	8/26/2011	6,819	6,823	3
<b>SET CBP 6,850'</b>				
STATE 1021-32J	8/26/2011	7,091	7,092	3
STATE 1021-32J	8/26/2011	7,117	7,118	3
STATE 1021-32J	8/26/2011	7,199	7,200	4
STATE 1021-32J	8/26/2011	7,292	7,293	4
STATE 1021-32J	8/26/2011	7,314	7,315	4
STATE 1021-32J	8/26/2011	7,354	7,356	3

STATE OF UTAH				FORM 15
DEPARTMENT OF NATURAL RESOURCES				AMENDED REPORT <input type="checkbox"/>
DIVISION OF OIL, GAS AND MINING				Original Filing Date: 11/27/2011
<b>DESIGNATION OF WORKOVER OR RECOMPLETION</b>				
1. Name of Operator KERR-MCGEE OIL & GAS ONSHORE, L.P.		2. Utah Account Number N2995		5. Well Name and Number STATE 1021-32J
3. Address of Operator P.O. Box 173779		City Denver	State CO	Zip 80217
4. Phone Number 720 929-6515		6. API Number 4304739133		
9. Location of Well Footage: 1802 FSL 2149 FEL County: UINTAH QQ, Sec, Twnp, Rnge: NWSE 32 100S 210E State: UTAH				7. Field Name NATURAL BUTTES
				8. Field Code Number 630
<b>COMPLETE ALL SECTIONS. ATTACH ADDITIONAL SHEETS IF NEEDED.</b>				
10. TYPE OF WORK (Check all that apply) <input type="checkbox"/> Production enhancement <input checked="" type="checkbox"/> Recompletion <input type="checkbox"/> Convert to injection <input type="checkbox"/> Repair well		11. WORK PERIOD Date work commenced: 8/25/2011 90 Days From Date work completed: 8/29/2011 Completion		
12. THE FOLLOWING EXPENSES FOR OPERATIONS ARE SUBMITTED FOR DESIGNATION AS WORKOVER OR RECOMPLETION EXPENSES:				
		<u>Expenses</u>		<u>Approved By State</u>
a. Location preparation and cleanup		0.00		0.00
b. Move-in, rig-up, and rig-down (including trucking)		1655.00		1655.00
c. Rig charges (including fuel)		17830.00		17830.00
d. Drill pipe or other working string		0.00		0.00
e. Water and chemicals for circulating fluid (including water hauling)		34727.00		34727.00
f. Equipment purchase		0.00		0.00
g. Equipment rental		13650.00		13650.00
h. Cementing		0.00		0.00
i. Perforating		17228.00		17228.00
j. Acidizing		0.00		0.00
k. Fracture stimulation		114229.00		114229.00
l. Logging services		0.00		0.00
m. Supervision and overhead		4400.00		4400.00
n. Other (itemize)		FLOWBACK CREW		11000.00
		PRESSURE TEST FRAC VALVES		1100.00
		0		0.00
		0		0.00
o. Total submitted expenses		215819.00		
p. Total approved expenses (State use only)				215819.00
13. LIST CONTRACTORS PROVIDING SERVICES VALUED AT MORE THAN \$3,000.				
Contractor		Location (City, State)		Services Provided
BLUE MOUNTAIN SERVICES		Vernal UT		ROUSTABOUT
CF WINN WELL SERVICE		Vernal UT		SUPERVISION
CHARLES HOLSTON INC		Vernal Ut		FRAC TANKS
DELSCO NORTHWEST INC		Roosevelt Ut		FLOWBACK CREW
HALLIBURTON ENERGY SERVICES INC		Vernal UT		CBPS
JW WIRELINE		ROOSEVELT UT		PERFERATING
MILES WELL SERVICE		NEOLA UT		RIG
NALCO ENERGY SERVICES		Vernal UT		CHEMICALS
RNI TRUCKING		ROOSEVELT UT		SWDTMAC FRAC FLUID
SUPERIOR WELL SERVICES		Vernal UT		FRAC
WEATHERFORD		VERNAL UT		BOP PACKER
14. LIST WORKING INTEREST OWNERS WHO TAKE PRODUCT IN KIND AND ARE AUTHORIZED TO SHARE IN THE TAX CREDIT.				
Name		Address	Utah Account No.	Percent of Interest
I hereby certify that this report is true and complete to the best of my knowledge.				
NAME (PLEASE PRINT) Sheila Wopsock		TITLE Regulatory Analyst		PHONE 435 781-7024

RECEIVED Nov. 27, 2011

SIGNATURE

Sheila Wopsock

DATE

November 27, 2011

E-MAIL

sheila.wopsock@anada

**RECEIVED** Nov. 27, 2011

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 6

**ENTITY ACTION FORM**

Operator: KERR MCGEE OIL & GAS ONSHORE LP Operator Account Number: N 2995  
Address: 1368 SOUTH 1200 EAST  
city VERNAL  
state UT zip 84078 Phone Number: (435) 781-7024

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
Various	NBU REVISION						UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
<i>E</i>	<i>Various</i>	<i>2900</i>	<i>3/13/2012</i>			<i>2/1/2012</i>	
Comments: MOVE THE ATTACHED WELLS INTO THE NATURAL BUTTES UNIT REVISION EFFECTIVE 02/01/2012. <i>72 wells</i> <i>5/31/2012</i>							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

**ACTION CODES:**

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

SHEILA WOPSOCK

Name (Please Print)

Signature

REGULATORY ANALYST

Title

5/30/2012

Date

RECEIVED

MAY 31 2012

Div. of Oil, Gas & Mining

## Entity Action Form Attachment for wells moved into the Natural Buttes Unit Effective 02/01/2012.

API	Well Name	QTR/QTR	Section	TWNSHP	RANGE	Producing Intervals
4304737079	FEDERAL 920-25I	NESE	15431	25 9S	20E	WASATCH/MESAVERDE
4304737080	FEDERAL 920-25H	SENE	15761	25 9S	20E	WASATCH/MESAVERDE
4304737081	FEDERAL 920-25A	NENE	15553	25 9S	20E	WASATCH/MESAVERDE from MVRD
4304739098	STATE 1021-28M	SWSW	16499	28 10S	21E	WASATCH To WSMVD
4304737918	FEDERAL 1021-26L	NWSW	16390	26 10S	21E	MESAVERDE To WSMVD
4304737919	FEDERAL 1021-26N	SESW	16391	26 10S	21E	WASATCH/MESAVERDE
4304737916	FEDERAL 1021-25O	SWSE	16277	25 10S	21E	WASATCH/MESAVERDE
4304739112	STATE 1021-31M	SWSW	16454	31 10S	21E	WASATCH To WSMVD
4304739127	STATE 1021-32P	SESE	16471	32 10S	21E	WASATCH/MESAVERDE
4304739128	STATE 1021-32O	SWSE	17513	32 10S	21E	WASATCH/MESAVERDE
4304739131	STATE 1021-32L	NWSW	16902	32 10S	21E	WASATCH/MESAVERDE
4304739133	STATE 1021-32J	NWSE	17539	32 10S	21E	WASATCH/MESAVERDE
4304739134	STATE 1021-32I	NESE	16905	32 10S	21E	WSMVD
4304739135	STATE 1021-32H	SENE	17528	32 10S	21E	WASATCH/MESAVERDE
4304735714	FEDERAL 1022-29H	SENE	15147	29 10S	22E	WASATCH/MESAVERDE
4304735715	FEDERAL 1022-29F	SENW	15162	29 10S	22E	WASATCH/MESAVERDE
4304735716	FEDERAL 1022-29B	NWNE	14982	29 10S	22E	WASATCH/MESAVERDE
4304735737	FEDERAL 1022-29I	NESE	15001	29 10S	22E	WASATCH/MESAVERDE
4304735738	FEDERAL 1022-29D	NWNW	15016	29 10S	22E	MESAVERDE To WSMVD
4304734862	FEDERAL 31-10-22	SESE	13879	31 10S	22E	MESAVERDE To WSMVD
4304735173	FEDERAL 1022-31D	NWNW	14132	31 10S	22E	WASATCH/MESAVERDE
4304736492	FEDERAL 1022-31N	SESW	16255	31 10S	22E	WASATCH/MESAVERDE
4304736493	FEDERAL 1022-31I	NESE	15089	31 10S	22E	WASATCH/MESAVERDE
4304736494	FEDERAL 1022-31G	SWNE	15075	31 10S	22E	WASATCH/MESAVERDE
4304736495	FEDERAL 1022-31F	SENE	15230	31 10S	22E	WASATCH/MESAVERDE
4304736574	FEDERAL 1022-31C	NENW	15090	31 10S	22E	WASATCH/MESAVERDE
4304736575	FEDERAL 1022-31J	NWSE	15214	31 10S	22E	WASATCH/MESAVERDE
4304736576	FEDERAL 1022-31L	NWSW	16376	31 10S	22E	WASATCH/MESAVERDE
4304734317	STATE 1-32	NESW	13419	32 10S	22E	WASATCH/MESAVERDE
4304734831	STATE 2-32	SESW	13842	32 10S	22E	MESAVERDE To WSMVD
4304734832	STATE 3-32	NWSW	13844	32 10S	22E	WASATCH/MESAVERDE
4304735095	STATE 1022-32J	NWSE	14097	32 10S	22E	WSMVD
4304735096	STATE 1022-32A	NENE	13914	32 10S	22E	WASATCH/MESAVERDE
4304735186	STATE 1022-32P	SESE	14131	32 10S	22E	MESAVERDE To WSMVD
4304735315	STATE 1022-32O	SWSE	14114	32 10S	22E	WASATCH/MESAVERDE
4304735647	STATE 1022-32H	SENE	14348	32 10S	22E	MESAVERDE To WSMVD
4304736413	STATE 1021-36O	SWSE	15619	36 10S	21E	WASATCH/MESAVERDE
*4304738157 WELL BELONGS TO QEP ENERGY CORP "GH 8-20-8-21" PERMIT NOT APPROVED						
4304734839	FEDERAL 1022-15F	SENW	14618	15 10S	22E	WASATCH/MESAVERDE
4304736414	STATE 1021-36J	NWSE	15651	36 10S	21E	WASATCH/MESAVERDE
4304738152	STATE 1021-36L	NWSW	16012	36 10S	21E	WASATCH/MESAVERDE
4304735440	FEDERAL 1022-15J	NWSE	14617	15 10S	22E	WASATCH/MESAVERDE
4304736415	STATE 1021-36I	NESE	15684	36 10S	21E	WASATCH/MESAVERDE
4304738845	STATE 1021-36D	NWNW	16455	36 10S	21E	WASATCH/MESAVERDE

4304750096	FEDERAL 1022-27H	SENE	17626	27 10S	22E	WASATCH/MESAVERDE
4304736416	STATE 1021-36H	SENE	15335	36 10S	21E	WASATCH/MESAVERDE
4304738846	STATE 1021-36E	SWNW	16523	36 10S	21E	WASATCH/MESAVERDE
4304735676	FEDERAL 1022-28L	NWSW	15110	28 10S	22E	WASATCH/MESAVERDE
4304736417	STATE 1021-36G	SWNE	15297	36 10S	21E	WASATCH/MESAVERDE
4304738847	STATE 1021-36F	SENW	16394	36 10S	21E	WASATCH/MESAVERDE
4304735713	FEDERAL 1022-28N	SESW	15145	28 10S	22E	WASATCH/MESAVERDE
4304736418	STATE 1021-36B	NWNE	14953	36 10S	21E	WASATCH/MESAVERDE
4304738848	STATE 1021-36N	SESW	16359	36 10S	21E	WASATCH/MESAVERDE
4304735735	FEDERAL 1022-28O	SWSE	15285	28 10S	22E	WASATCH/MESAVERDE from MURD
4304736419	STATE 1021-36A	NENE	15035	36 10S	21E	WASATCH/MESAVERDE
4304738849	STATE 1021-36K	NESW	16084	36 10S	21E	WASATCH/MESAVERDE
4304735736	FEDERAL 1022-28M	SWSW	15286	28 10S	22E	WASATCH/MESAVERDE
4304736420	STATE 1021-36P	SESE	15372	36 10S	21E	WASATCH/MESAVERDE
4304738850	STATE 1021-36C	NENW	16396	36 10S	21E	WASATCH/MESAVERDE
4304734861	FEDERAL 29-10-22	SESE	14006	29 10S	22E	MESAVERDE TO WSMVD
4304735577	FEDERAL 1022-33O	SWSE	15080	33 10S	22E	WASATCH/MESAVERDE
4304735739	FEDERAL 1022-33E	SWNW	15193	33 10S	22E	WASATCH/MESAVERDE
4304735740	FEDERAL 1022-33M	SWSW	15373	33 10S	22E	WASATCH/MESAVERDE
4304735741	FEDERAL 1022-33L	NWSW	15511	33 10S	22E	WASATCH/MESAVERDE
4304735742	FEDERAL 1022-33G	SWNE	15404	33 10S	22E	WASATCH/MESAVERDE from MURD
4304735743	FEDERAL 1022-33C	NENW	15405	33 10S	22E	WASATCH/MESAVERDE
4304735744	FEDERAL 1022-33A	NENE	15539	33 10S	22E	WASATCH/MESAVERDE
4304737105	FEDERAL 1022-33D	NWNW	16502	33 10S	22E	WASATCH/MESAVERDE
4304737106	FEDERAL 1022-33F	SENW	16560	33 10S	22E	WASATCH/MESAVERDE from WSTC
4304737107	FEDERAL 1022-33K	NESW	16124	33 10S	22E	WASATCH/MESAVERDE
4304737109	FEDERAL 1022-33N	SESW	16126	33 10S	22E	WASATCH/MESAVERDE
4304737110	FEDERAL 1022-33B	NWNE	16561	33 10S	22E	WASATCH/MESAVERDE
4304735810	STATE 1021-36E	SWNW	14295	36 10S	21E	WASATCH/MESAVERDE

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ML-21577
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b> NATURAL BUTTES
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> STATE 1021-32J
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1802 FSL 2149 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWSE Section: 32 Township: 10.0S Range: 21.0E Meridian: S		<b>9. API NUMBER:</b> 43047391330000
<b>PHONE NUMBER:</b> 720 929-6514		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 8/19/2011	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input checked="" type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>	
<input type="checkbox"/> DRILLING REPORT Report Date:		
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  The operator has concluded the wellhead/casing repairs on the subject well location. Please see the attached chronological history for details of the operations.		
Accepted by the Utah Division of Oil, Gas and Mining <b>FOR RECORD ONLY</b> July 26, 2012		
<b>NAME (PLEASE PRINT)</b> Jaime Scharnowski	<b>PHONE NUMBER</b> 720 929-6304	<b>TITLE</b> Regulatory Analyst
<b>SIGNATURE</b> N/A	<b>DATE</b> 7/17/2012	



**US ROCKIES REGION**  
**Operation Summary Report**

Well: STATE 1021-32J			Spud Conductor: 2/11/2010				Spud Date: 2/19/2010	
Project: UTAH-UINTAH			Site: STATE 1021-32J				Rig Name No: MILES 3/3	
Event: WELL WORK EXPENSE			Start Date: 8/18/2011				End Date: 8/19/2011	
Active Datum: RKB @5,331.00ft (above Mean Sea Leve			UWI: STATE 1021-32J					
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
8/18/2011	7:00 - 7:15	0.25	MAINT	48		P		HSM POOH TBG SET CIBP
	7:15 - 8:00	0.75	MAINT	30	A	P		KILL WELL, W/20 BBLS, WTR DN, TBG, & 20 BBLS, DN CSG, ND, WH, NU, BOPS, RU, FLOOR, & TBG EQUIPMENT.
	8:00 - 12:00	4.00	MAINT	31	I	P		POOH W/ 42, JTS, J-55 N-80 TBG LD ON TRAILER, STAND REST BACK,
	12:00 - 15:30	3.50	MAINT	34	I	P		WAIT ON WIERLINE, MIRU JW WIRELINE, PU RIH W 4 1/2 GR & JB, TO 7397 ', STACKED OUT W GR,&JB CALLED BJ HE SAID WE WERE OKAY TO SET PLUG, POOH, RIH W BAKER 4 1/2 10 K, CIBP SET @ 7388 ' POOH RD, WIRELINE
	15:30 - 20:00	4.50	MAINT	31	I	P		RIH W 228 JTS, J-55 2 3/8 TBG POOH W TBG LD ON TRAILER, TOTAL # JTS ON TRAILER 270 SWI, SDFN.
8/19/2011	7:00 - 7:15	0.25	MAINT	48		P		HSM REVIEWED BACK-OFF PROCEDURE
	7:15 - 9:00	1.75	MAINT	30	A	P		RD, FLOOR, ND, BOPS W/ CSG BOWL, RU FLOOR, NU PWR SWVL
	9:00 - 12:00	3.00	MAINT					PU, INTERNAL CUTTER, RIH CUT 4 1/2 CSG 3' F/ SURFACE, POOH LD INTERNAL CUTTER & MANDRAL, PU 4 1/2 OVERSHOT, RIH LATCH ON FISH, MIRU CSG CREW, & JW WIRELINE STRING SHOT COLLAR BACK-OFF 4 1/2 CGS, PU NEW CSG, PUP, JNT, TAG, CSG, TOP THREAD INTO CSG, TORQUE TO 7000# W/ 14 ROTATIONS, PU CSG TO 90,000# TENSION.
	12:00 - 13:00	1.00	MAINT	33	C	P		MIRU B&C QUICK TEST, PT 4 1/2 CSG TO 1000# FOR 15 MINS LOST 8 PSI IN 15 MINS, PT. 4 1/2 CSG TO 3500# FOR 30 MINS LOST 44 PSI IN 30 MINS RD, B&C QUICK TEST.
	13:00 - 14:30	1.50	MAINT			P		MIRU WEATHERFORD TECH., INSTALL C-21 SLIPS W 90,000# TENSION, CUT & DRESS 4 1/2 CSG STUB, INSTALL CROSS OVER SPOOL.
	14:30 - 17:00	2.50	MAINT	30	A	P		NU, WH. FILL 4 1/2 CSG & SURFACE W T-MAC SWI,SNFWD,RDMO, TO NBU 1021-32 G, SPOT RIG TO DRILLOUT ON 8/22/11.